

## Nemani, Nate

---

**From:** McNichol, David <DMcNichol@trcsolutions.com>  
**Sent:** Tuesday, October 14, 2014 7:38 AM  
**To:** Nemani, Nate  
**Cc:** Galacki, Walter; sam@apollodismantle.com  
**Subject:** SPX Corp. Former Lindberg Facility, 304 Hart St., Watertown, WI

**Categories:** Red Category

Dear Mr. Nemani:

This email, on behalf of SPX Corporation, is to confirm our conversations of last week regarding the captioned facility.

SPX Corp. has had a change in plans and now wishes to completely demolish and remediate the facility rather than the previous plan (and EPA approval) to clean the contaminated PCB floor areas and effectively encapsulate the cleaned areas. We believe that this complete removal and complete demolition represents a permanent remedy for the facility and is therefore better.

We would propose to remove the PCB contaminated floor areas to the identical areal extent (with one exception) that the previously approved remedy proposed. The very same information that was submitted to EPA for that approval would again be relied upon. The removal would occur in the shaded areas shown on Drawing "Figure 7" from the "PCB Assessment Report" dated August 11, 2010 by Delta Consultants. Thus areas with a PCB concentration greater than 10 mg/kg will be removed and properly transported and disposed.

The exception involves the large building segment in the NW, in that area we propose to remove the floor beyond what the data show. Rather than estimate the 10 mg/kg line between cores we will remove to the less than 10 mg/kg core adjacent and beyond the shaded area. That way we believe we are being more conservative and complete, not having to rely so much on any post removal samples. We believe this further makes sense because most of the remainder of the shaded floor areas are bounded by walls-thus providing a practical limit for concrete floor removal. (The small outside area will have a removal of the truck pad and soils which will need to be confirmed by post-ex. samples.)

SPX has recently funded this work and hired a contractor, thus this request is very timely and we would hope for a reasonably timely response. We thank you for your consideration and review and would readily answer any questions.

Very truly yours,

Dave McNichol  
Senior Consultant



500 Bic Drive, Ste. 103, Milford, CT 06461  
T: 203.876.1453 | F: 203.876.1486 | C: 203.856.8388

dmcnichol@trcsolutions.com







## Nemani, Nate

---

**From:** Schmoller, Michael R - DNR <Michael.Schmoller@wisconsin.gov>  
**Sent:** Tuesday, November 25, 2014 3:29 PM  
**To:** Nemani, Nate  
**Subject:** FW: SPX, Hart Street, Watertown

fyi

**We are committed to service excellence.**

Visit our survey at <http://dnr.wi.gov/customersurvey> to evaluate how I did.

R. Michael Schmoller  
Phone: 608-275-3303  
[Michael.schmoller@wisconsin.gov](mailto:Michael.schmoller@wisconsin.gov)

---

**From:** Schmoller, Michael R - DNR  
**Sent:** Tuesday, November 25, 2014 3:28 PM  
**To:** 'dmcnichol@trcsolutions.com'; Hanefeld, Linda S - DNR  
**Cc:** 'walter.galacki@spx.com'  
**Subject:** SPX, Hart Street, Watertown

Dave

I have looked at the demolition and waste management proposal for this property. For the most part the proposal seems acceptable. There are two concerns. These are:

If contaminated material is placed back on site as fill, those areas will be may need capping or further remedial measures. In Wisconsin the direct contact criteria for PCBs is .22 ppm for residential areas and .74 ppm in commercial and industrial sites. As proposed it is possible some fill material may exceed these criteria.

As proposed there is no provision for subslab soil sampling based on the apparent lack of migration of PCBs through the concrete. Our experience shows us that in an industrial setting where PCBs were handled for nearly 20 years there is often soil contamination as a result of movement through floor cracks, etc. To comply with state requirements and meet our closure criteria subslab soils sampling will be necessary.

Please contact me about these issues as soon as possible.

Mike

**We are committed to service excellence.**

Visit our survey at <http://dnr.wi.gov/customersurvey> to evaluate how I did.

R. Michael Schmoller  
Hydrogeologist  
Wisconsin Department of Natural Resources  
Phone: 608-275-3303  
Cell Phone: 608-576-0183  
[Michael.schmoller@wisconsin.gov](mailto:Michael.schmoller@wisconsin.gov)



[dnr.wi.gov](http://dnr.wi.gov)









## Nemani, Nate

---

**From:** McNichol, David <DMcNichol@trcsolutions.com>  
**Sent:** Monday, April 11, 2016 10:07 AM  
**To:** Nemani, Nate  
**Subject:** FW: Requested Information  
**Attachments:** 218588-006\_Results.pdf; 218588-008\_Proposed Borings.pdf; 2185880000PH2-001\_01182016.xlsx

-----Original Message-----

From: McNichol, David  
Sent: Wednesday, March 30, 2016 2:29 PM  
To: Nemani, Nate <nemani.nate@epa.gov>  
Cc: Galacki, Walter <walter.galacki@spx.com>  
Subject: FW: Requested Information

Nate Hi

I have been meaning to share this with you for weeks. My apologies.

I thought that since I had updated Mr. Ackerman it would be a reasonable and good thing if I updated you also.

After you have had the opportunity to review this, please call if you would like to discuss.

At present we have done further work on SPX property, however, we've not been given access to complete further investigation of the **nonres** properties.

Best

Dave

Dave McNichol  
Senior Consultant

500 Bic Drive, Ste. 103, Milford, CT 06461  
T: 203.876.1453 | F: 203.876.1486 | C: 203.856.8388

dmcnichol@trcsolutions.com



-----Original Message-----

From: McNichol, David

Sent: Friday, February 12, 2016 4:07 PM

To: Ackerman, Jeffrey A - DNR <Jeffrey.Ackerman@wisconsin.gov>

Cc: Galacki, Walter <walter.galacki@spx.com>; Braun, Nathan <NBraun@trcsolutions.com>

Subject: Fw: Requested Information

Jeff Hi

The attached items are enough, I believe, to enable you to see the complete PCB picture for SPX and the abutting properties. You should also have received this week a Draft Remedial Action Completion report which includes the figure showing the sub-slab soil results associated with the building demo and remediation (all less than 0.74 mg/kg). Taken as a whole I believe you can evaluate just what information we have, shallow or at depth, and also understand what we are proposing to complete the delineation to WI residential soil stds.

Talk to you when I'm back the first week in March.

Best

Dave

---

From: Braun, Nathan

Sent: Friday, February 12, 2016 3:40 PM

To: McNichol, David

Subject: Requested Information

Your message is ready to be sent with the following file or link attachments:

218588-006\_Results

218588-008\_Proposed Borings

2185880000PH2-001\_01182016

Note: To protect against computer viruses, e-mail programs may prevent sending or receiving certain types of file attachments. Check your e-mail security settings to determine how attachments are handled.



Table 1  
PCB Sample Results  
SPX - Lindbergh/MPH  
Watertown, Wisconsin

BORING ID	DEPTH RANGE (inches bgs)	TOTAL PCB (mg/kg)
B-1A	12-17	0.11
B-1B	55-60	ND
B-1C	0-6	<b><u>0.29</u></b>
B-2A	9-14	ND
B-2B	36	ND
B-2C	60	ND
B-3A	9-13	ND
B-3B	33-37	ND
B-4A	10-14	ND
B-4B	55-60	ND
B-5A	19-24	0.15
B-5B	55-60	ND
B-6A	24-29	ND
B-6B	55-60	ND
B-7A	19-24	ND
B-7B	55-60	ND
B-8A	19-24	ND
B-8B	55-60	ND
B-9A	20-24	ND
B-9B	55-60	ND
B-10A	19-24	<b><u>110</u></b>
B-10B	55-60	<b><u>96</u></b>
B-11A	16-21	ND
B-11B	55-60	ND
B-12A	9-14	<b><u>0.51</u></b>
B-12B	24-29	ND
B-12C	55-60	ND
B-13A	6-11	ND
B-13B	55-60	ND
B-14A	0-6	0.12
B-14B	55-60	ND
B-14C	115-120	ND
B-15A	6-11	ND
B-15B	55-60	ND
B-16A	0-6	<b><u>0.29</u></b>
B-16B	55-60	ND
B-16C	115-120	ND
B-17A	17-22	ND
B-17B	55-60	ND

BORING ID	DEPTH RANGE (inches bgs)	TOTAL PCB (mg/kg)
B-18A	0-6	<b><u>1.1</u></b>
B-18B	55-60	ND
B-19A	16-21	0.11
B-19B	55-60	ND
B-19C	115-120	ND
B-20A	12-17	ND
B-20B	55-60	ND
B-21A	6-11	<b><u>1.1</u></b>
B-21B	55-60	ND
B-22A	10-15	<b><u>0.68</u></b>
B-22B	55-60	ND
B-23A	10-15	0.11
B-23B	55-60	ND
B-24A	12-17	ND
B-24B	55-60	ND
B-25A	6-12	0.22 <sup>(4)</sup>
B-25B	55-60	ND
B-25C	115-120	ND
B-26A	6-11	ND
B-26B	55-60	ND
B-27A	6-11	<b><u>0.61</u></b>
B-27B	55-60	ND
B-28A	12-17	<b><u>1.7</u></b>
B-28B	55-60	ND
B-29A	0-9	<b><u>14</u></b>
B-29B	55-60	ND
B-30A	8-13	<b><u>9.4</u></b>
B-30B	55-60	ND
B-31A	12-17	ND
B-31B	55-60	ND
B-32A	6-11	<b><u>1.5</u></b>
B-32B	55-60	ND
B-33A	6-11	0.19
B-33B	55-60	ND
B-34A	4-9	<b><u>0.23</u></b>
B-34B	55-60	ND
B-35A	4-9	<b><u>0.85</u></b>
B-35B	55-60	ND
B-36A	6-11	<b><u>3.9</u></b>

Notes:

1. Samples (TP & B-1 through B-33) collected on November 2 & 5, 2015, & B-34 through B-41 on 01/08/2016 by TRC, Inc.
2. ND = Non-detected - concentration below detection limit.
3. Bold & underlined results exceed the Wisconsin Residential Cleanup Standard of 0.221 mg/kg
4. Value equals the Wisconsin Residential Cleanup Standard.

Created by: A. Schroeder 11/15/2015, updated 1/18/16



Checked by: N. Braun 11/16/15

**Table 1 - Continued  
PCB Sample Results  
SPX - Lindbergh/MPH  
Watertown, Wisconsin**

BORING ID	DEPTH RANGE (inches bgs)	TOTAL PCB (mg/kg)
B-36B	55-60	ND
B-37A	6-11	ND
B-37B	55-60	ND
B-38A	19-24	ND
B-38B	55-60	ND
B-38C	115-120	ND
B-39A	19-24	<b><u>1.5</u></b>
B-39B	55-60	<b><u>0.71</u></b>
B-39C	115-120	ND
B-40A	19-24	ND
B-40B	55-60	ND
B-40C	115-120	ND
B-41A	19-24	<b><u>39</u></b>
B-41B	55-60	<b><u>200</u></b>
B-41C	115-120	0.22 <sup>(4)</sup>
<b>nonresponsiv</b>	3	0.19
TP-1	12 & 96	<b><u>34</u></b> & ND
TP-2	36 & 108	ND
TP-3	36 & 96	ND

Notes:

1. Samples (TP & B-1 through B-33) collected on November 2 & 5, 2015, & B-34 through B-41 on 01/08/2016 by TRC, Inc.
2. ND = Non-detect - concentration below detection limit.
3. Bold & underlined results exceed the Wisconsin Residential Cleanup Standard of 0.221 mg/kg
4. Value equals the Wisconsin Residential Cleanup Standard.

Created by: A. Schroeder 11/15/2015, updated 1/18/16

Checked by: N. Braun 11/16/15, updated 1/20/16





LEGEND

PROPOSED GEOPROBE® SOIL BORING LOCATION

PROPOSED GEOPROBE® SOIL BORING LOCATION - SAMPLE WILL BE HELD

GEOPROBE® SOIL BORING

NOTES

1. BASE MAP IMAGERY FROM GOOGLE EARTH PRO & PARTNERS, 2014.

2. LABORATORY RESULTS ARE LOCATED ON TABLE 1 FOR THE TEST PITS AND GEOPROBE® BORINGS.

3. BORINGS B-1 THROUGH B-33 WERE COMPLETED ON 11/05/2015.

4. BORINGS B-34 THROUGH B-41 WERE COMPLETED ON 01/08/1991.

5. TEST PITS WERE COMPLETED ON 11/02/2015.

0

40

80

Feet

1" = 40'

1:480

DRAFT

PROJECT:

SPX - LINDBERGH/MPH  
WATERTOWN, WISCONSIN

SHEET TITLE:

PROPOSED SOIL BORINGS

DRAWN BY:

SUEMNICHT R

CHECKED BY:

APPROVED BY:

DATE:

JANUARY 2016

SCALE:

1: 480

DATE PRINTED:

PROJ. NO.

218558

FILE NO.

218558-008.mxd

FIGURE 1


TRC

708 Heartland Trail, Suite 3000  
Madison, WI 53717  
Phone: 608.826.3600  
www.trcsolutions.com









**LEGEND**

0.718  
⊗ PREVIOUS PCB SOIL SAMPLE LOCATION & CONCENTRATION (mg/kg)  
■ TEST PIT LOCATION  
⊗ GEOPROBE® SOIL BORING (YELLOW OUTLINED SOIL BORING ID DEPICTS A NON-DETECT RESULT)  
B-1A (0.11) SAMPLE RESULTS DO NOT EXCEED THE RESIDENTIAL CLEANUP STANDARD OF 0.221 mg/kg  
B-10A (110) SAMPLE RESULTS EXCEED THE RESIDENTIAL CLEANUP STANDARD OF 0.221 mg/kg  
B-10A (0.22) SAMPLE RESULTS EQUAL THE RESIDENTIAL CLEANUP STANDARD OF 0.221 mg/kg  
(0.19) SAMPLE COLLECTED BY MARK KNIGHT, CONSULTANT FOR MR. **nonre**

**NOTES**

1. BASE MAP IMAGERY FROM GOOGLE EARTH PRO & PARTNERS, 2014.

2. LABORATORY RESULTS ARE LOCATED ON TABLE 1 FOR THE TEST PITS AND GEOPROBE® BORINGS.

3. BORINGS B-1 THROUGH B-33 WERE COMPLETED ON 11/05/2015.

4. BORINGS B-34 THROUGH B-41 WERE COMPLETED ON 01/08/2016.

5. TEST PITS WERE COMPLETED ON 11/02/2015.

0 40 80 Feet

1" = 40'

1:480

DRAFT

PROJECT: SPX - LINDBERGH/MPH  
WATERTOWN, WISCONSIN

SHEET TITLE: SOIL BORING & SAMPLE LOCATION RESULTS

DRAWN BY: SUEMNICHT R

CHECKED BY:

APPROVED BY:

DATE: JANUARY 2016

SCALE: 1: 480

DATE PRINTED:

PROJ. NO. 218558

FILE NO. 218588-006.mxd

FIGURE 2

TRC

708 Heartland Trail, Suite 3000  
Madison, WI 53717  
Phone: 608.826.3600  
www.trcsolutions.com








LAW OFFICES OF  
CAREY S. ROSEMARIN, P.C.  
847-897-8000  
500 SKOKIE BOULEVARD, SUITE 510  
NORTHBROOK, ILLINOIS 60062

Fax: 312-896-5786  
csr@rosemarinlaw.com

April 6, 2016

**CERTIFIED MAIL**  
**RETURN RECEIPT REQUESTED**



**TO:** See Attached Service List

**Re:** • *SPX Corporation Property Located at 304 Hart Street, Watertown, Wisconsin*

• *Notices of Intent to Sue Pursuant to:*

- 1) *Resource Conservation and Recovery Act, 42 U.S.C. § 6972(a)(1)(B)*
- 2) *Toxic Substances Control Act, 15 U.S.C. § 2619(1)(a)*
- 3) *Clean Air Act, 42 U.S.C. § 7604(a)(1)*

Dear Notice Recipients:

This law firm represents **nonrespo** [REDACTED] and their son and daughter-in-law, **nonresponsive** [REDACTED] (collectively, the "**nonresp**"). This letter comprises three notices of intent to sue the persons identified herein as "Respondents" by each of the **nonresp**. One notice is issued pursuant to the "Citizen suits" provisions of the Resource Conservation Recovery Act, 42 U.S.C. § 6972(a)(1)(B); another is issued pursuant to the "Citizens' civil actions" provisions of the Toxic Substances Control Act, 15 U.S.C. § 2619(1)(a); and the final notice is issued pursuant to the "Citizen suits" provisions of the Clean Air Act, 42 U.S.C. § 7604(a).

The persons to whom these notices are directed ("Respondents") are SPX Corporation, of Charlotte, North Carolina ("SPX"); Apollo Dismantling, Inc., of Niagara Falls, New York ("Apollo"); TRC Solutions, Inc., of Windsor, Connecticut ("TRC"); Badger Asbestos Abatement, Inc., of Milwaukee, Wisconsin and Badger Asbestos and Mold Abatement, Inc., of New Berlin, Wisconsin (collectively, "Badger")<sup>1</sup>.

**nonresponsive** [REDACTED]

They own the parcel of property at that address, as well as three other parcels on **nonr** [REDACTED]

<sup>1</sup> Records that have been made available to date are ambiguous as to whether Badger Asbestos Abatement, Inc., (which Wisconsin Secretary of State records show to be dissolved) or Badger Asbestos and Mold Abatement, Inc., or both, were involved in the demolition and/or remediation of the SPX facility. Therefore, this notice is being sent to both entities.



nonr Street, commonly known as nonresponsive. The parcels at non nonres are adjacent to each other and together, serve as the site of nonresponsive nonresp principal residence, which they have continuously occupied throughout all relevant time periods. nonresponsiv also occupied that residence, but no longer do so. Single family homes are present on and nonresponsive and they were also occupied during all relevant time periods. A children's day care center is located on the west side of nonrespo Street; its address is believed to be non.

All four of the nonresp parcels abut industrial property to the east, commonly known as 304 Hart Street, Watertown, Wisconsin. That property is owned by SPX and consists of approximately 5.3 acres. Until recently, a large industrial facility was located on the property. Transformers and other equipment were formerly manufactured there. The facility ceased to operate in approximately 2005 and appears to have remained idle for the ensuing decade. But as explained below, the facility harbored large quantities of asbestos and polychlorinated biphenyls ("PCBs").

In 1999 Badger conducted an asbestos survey for SPX's predecessor. The survey disclosed a considerable amount of asbestos throughout many areas of the facility in varying stages of deterioration. Badger's report stated, "... many areas within your plant require at least the minimum response actions noted within this report to protect your workers from asbestos exposure."

In 2009 SPX reportedly discovered that concrete in the facility was contaminated with PCBs and the following year SPX engaged Delta Consultants, of Shoreview, Minnesota ("Delta") to determine the extent of contamination. Delta confirmed the existence of Aroclor 1260 throughout large areas of the facility, particularly on the concrete floors, and reported concentrations of up to 3,310 ppm of Aroclor 1260.

In or around 2014 SPX decided to demolish the facility. It retained TRC to oversee the demolition, as well as the remediation of both the asbestos and the PCBs. The demolition appears to have been accomplished between February and July 2015, and was performed by Apollo. Badger was engaged to perform the asbestos abatement at the facility, and Apollo may also have participated in that project. It is believed that the asbestos abatement was conducted on various dates between October 2014 and July 2015.

On or about December 22, 2014, TRC submitted a document entitled, "Self-Implementing On-Site Cleanup and Disposal of PCB Remediation Waste" ("PCB Plan"), purportedly written pursuant to 40 CFR 761.61, to U.S.EPA Region 5. The PCB Plan stated that SPX would remediate PCBs to 0.74 ppm, Wisconsin's PCB soil cleanup standard for industrial/commercial property uses. It also stated the property would not be suitable for residential use; Wisconsin's PCB soil cleanup standard for residential property uses was 0.22 ppm. WI ADC § 720.07.



U.S.EPA communicated its conditional approval of the PCB Plan by a letter dated February 2, 2015. U.S.EPA's conditions required SPX to submit a completion report, containing verification sampling results and other information, within 60 days of completion of the remediation. Apollo performed the PCB cleanup and demolition.

While the industrial facility was still standing, its western wall was separated from the **nonres** residence and the other **nonres** parcels by only a narrow walkway. Therefore, it was obvious that precautions would have to be taken to avoid the release of PCBs and asbestos to the **nonresp** properties. Yet, on more than one occasion, asbestos inspections by the Wisconsin Department of Natural Resources ("WDNR") found visible emissions to the outside air, and regulated asbestos-containing material strewn about the facility in violation of 40 CFR § 61.145. Additionally, the PCB removal and demolition were conducted recklessly, and caused the release of large quantities of PCB-laden particulates, which settled on the **nonresp** properties and presumably elsewhere. Immediately after the demolition commenced, the **nonresp** experienced the onset of various health problems, including acute sinusitis, lymphadenopathy, conjunctivitis and bronchitis, which their physician contemporaneously attributed to their exposure to the demolition dust.

The carelessness with which the remediation and demolition were undertaken was graphically shown in the video contained on the enclosed disc. The video was taken and narrated by Ms. **nonres** on April 3, 2015, while she was standing at the rear (east side) of the residence. It shows the demolition and large clouds of wind-blown demolition dust drifting toward the **nonresp** properties.

**nonresponsive** reported this matter to both the Watertown Health Department and the WDNR, both of which contacted SPX through both TRC and Apollo. About two months after the demolition began, SPX caused TRC to collect surface soil samples from the **nonresp** properties, including one from the vegetable garden in the backyard of the **nonres** residence. The laboratory analytical results showed the vegetable garden sample to contain 5.81 ppm of Aroclor 1260.

SPX and other Respondents blatantly violated 40 CFR §761.79(e)(1), which reads in its entirety as follows:

- (e) Limitation of exposure and control of releases.
  - (1) Any person conducting decontamination activities under this section shall take necessary measures to protect against release of PCBs to the environment from the decontamination area.

SPX and other Respondents have violated and continue to violate 40 CFR §761.61 because they have not conducted a cleanup verification in accordance with 40 CFR § 761.61(a)(6). They have also violated the conditions of the February 2, 2015 approval because




Notices of Intent to Sue  
SPX Corporation Site, Watertown, WI  
April 6, 2016  
Page 4 of 7

they have not submitted to U.S.EPA: i) a completion report (due within 60 days of the completion of the plan); nor ii) a draft deed notice restricting the future use of the property.

Additionally, SPX and other Respondents have failed to comply in any fashion with 40 CFR Part G, the "Spill Cleanup Policy." SPX and other Respondents discovered that the demolition contaminated the **nonresp** vegetable garden with Aroclor 1260 fully ten months ago, and subsequently discovered it had similarly contaminated the **nonresp** properties over a much broader area. Yet, neither SPX nor other Respondents have complied with either the reporting requirements or remedial requirements of 40 CFR §61.125.

Respondents' continuing violations of the PCB regulations cited above subject them to a civil action under 15 U.S.C. § 2619, and their repeated violations of the asbestos regulations cited above subject them to a civil action under 42 U.S.C. § 7604(a). By virtue of these actions and by virtue of Respondents' continued failure to properly address and remediate the release of asbestos and PCBs, Respondents have contributed to and are contributing to the disposal of hazardous wastes which may present an imminent and substantial endangerment to health or the environment. Such contribution thereby subjects Respondents to a citizen suit under 42 U.S.C. § 6972(a)(1)(B).

Very truly yours,



Carey S. Rosemarin



Service List

*Via Certified Mail*  
*Return Receipt Requested*  
w/enclosed disc

United States

Gina McCarthy  
Administrator  
U.S. Environmental Protection Agency  
William Jefferson Clinton Building  
1200 Pennsylvania Avenue, N. W.  
Mail Code 1101A  
Washington, DC 20460

Robert A. Kaplan  
Acting Regional Administrator  
Region 5  
77 West Jackson Boulevard  
Mail Code R-19J  
Chicago, IL 60604-3507

State of Wisconsin

Office of Governor Scott Walker  
115 East Capitol  
Madison, WI 53702

Cathy L. Stepp  
Secretary  
Wisconsin Department of Natural Resources  
101 South Webster Street  
P.O. Box 921  
GEF2 DNR Central Office  
Madison, WI 53707-7921



Notices of Intent to Sue  
SPX Corporation Site, Watertown, WI  
April 6, 2016  
Page 6 of 7

**SPX Corporation**

Gene Lowe  
President and Chief Executive Officer  
SPX Corporation  
13320-A Ballantyne Corporate Place  
Charlotte, NC 28277

CT Corporation System  
Registered Agent for SPX Corporation  
8020 Excelsior Drive  
Suite 200  
Madison, WI 53717

**Apollo Dismantling Services, LLC**

Samuel DeFranks  
President  
Apollo Dismantling Services, LLC  
4511 Hyde Park Boulevard  
2<sup>nd</sup> Floor  
Niagara Falls, NY 14305

Business Filings Incorporated  
Registered Agent for Apollo Dismantling Services, LLC  
8020 Excelsior Drive, Suite 200  
Madison, WI 53717

**TRC Solutions, Inc.**

Christopher P. Vincze  
Chairman and Chief Executive Officer  
TRC Companies, Inc.  
9685 Research Drive  
Irvine, CA 92618

C T Corporation System  
Registered Agent for TRC Solutions, Inc.  
8020 Excelsior Drive, Suite 200  
Madison, WI 53717



Notices of Intent to Sue  
SPX Corporation Site, Watertown, WI  
April 6, 2016  
Page 7 of 7

**Badger Asbestos and Mold Abatement, Inc.**

Mark J. Andrus  
Registered Agent  
Badger Asbestos and Mold Abatement, Inc.  
5255 S. Brennan Drive  
New Berlin, WI 53146

**Badger Asbestos Abatement, Inc.**

Robert Frank Semrad  
Registered Agent  
Badger Asbestos Abatement, Inc.  
2400 Merlin Way  
Brookfield, WI 53045







## Nemani, Nate

---

**From:** Galacki, Walter <walter.galacki@spx.com>  
**Sent:** Wednesday, October 22, 2014 9:58 AM  
**To:** Nemani, Nate  
**Cc:** dmcnichol@trcsolutions.com; Baker, Susan; sam@apollodismantle.com  
**Subject:** FW: Watertown EPA PCB letter  
**Attachments:** USEPA Ltr dtd 102214 - Lindberg Facility, Watertown, WI.pdf

Hello Nate, I have not had a chance yet to speak with you regarding SPX's TPH Lindberg, Watertown WI site, but in view of the time sensitivity and your recent discussion with our consultant, Dave McNichol of TRC, I wanted to formalize our requested PCB remediation approval change request (attached). I am over-nighting a hard copy of the letter and attachments. If you by chance have the time to review or see any need for immediate changes to our letter that would help expedite the Agency's review – please call me. We are trying to get certain aspects of the demo worked out and secured before winter sets in, and as such, your timely review would be most appreciated.

Thank you,



**Walter Galacki**  
Director, Environmental

SPX Corporation  
13320 Ballantyne Corporate Place  
Charlotte, NC 28277  
Tel: (704)-808-3751  
Cell: (704) 724-1743  
Fax: (704) 752-4578  
e-Mail: [walter.galacki@spx.com](mailto:walter.galacki@spx.com)

The information contained in this electronic mail transmission is intended by SPX Corporation for the use of the named individual or entity to which it is directed and may contain information that is confidential or privileged. If you have received this electronic mail transmission in error, please delete it from your system without copying or forwarding it, and notify the sender of the error by reply email so that the sender's address records can be corrected.









Writers Direct Dial: 704-808-3751  
Writers Direct Fax: 704-752-4578  
E-Mail Address: [walter.galacki@spx.com](mailto:walter.galacki@spx.com)

December 22, 2014

USEPA  
Region 5  
TSCA/PCB Coordinator  
77 West Jackson Boulevard  
Chicago, IL 60604-3590  
Attn: Nate Nemani, L-8J

Re: SPX Corporation former Lindberg Facility  
304 Hart Street  
Watertown, WI 53094  
Revised Report and Cleanup Plan

Gentlemen:

As recently discussed between TRC, SPX's environmental consultant, and USEPA's Nate Nemani, SPX is submitting this revised information to notify and certify to the Agency and all concerned (the EPA Regional Administrator, the Secretary of the WI DNR, Jefferson County, and the City of Watertown) that SPX intends to conduct a "self-implementing on-site cleanup and disposal of PCB remediation waste" for the captioned site.

SPX had previously received EPA's approval for a partial removal of PCB surficially contaminated concrete flooring and encapsulation of other flooring (40 CFR 761.61 (c)) dated 28 March 2011. As discussed, based on the deteriorating condition of the building and in consultation with the City, SPX has decided to demolish the building and all associated structures and completely remediate the facility in accord with 40 CFR 761.61 (a)(3).

Enclosed is documentation covering the nature of the PCB contamination, the summary of procedures and methods for sampling, characterization and analysis, the location and extent of the contamination, and a cleanup plan including schedule, disposal plan and the demolition and remedial approach.

SPX CORPORATION  
13320 BALLANTYNE CORPORATE PLACE  
CHARLOTTE, NC 28277-2706  
UNITED STATES OF AMERICA

[www.spx.com](http://www.spx.com)




Nate Nemani, USEPA  
December 22, 2014  
Page 2

Since we believed that we were close to an EPA approval some time ago, we are asking for an expedited review of this material in order that our demolition and remediation contractor may continue with his work at the site. Should you need any further information please contact our consultant, Dave McNichol of TRC immediately.

Thank you in advance for your attention to this matter.

Very truly yours,



Walter Galacki  
Director Environmental  
For SPX Corporation, Owner and Operator and Successor in Interest of the  
former SPX Lindberg site

W/enclosures

CC: Jefferson County Health Department, Environmental Health Section  
WI DNR, Remediation and Redevelopment Program  
City of Watertown, J.J. Holloway, PE  
TRC, Dave McNichol  
Nixon Peabody, Al Floro



**SELF-IMPLEMENTING ON-SITE  
CLEANUP AND DISPOSAL OF PCB  
REMEDIATION WASTE**

**November 2014**

**REVISED December 19, 2014**

**SPX LINDBERG FACILITY,  
304 Hart Street, Watertown, WI**

**TRC Project No.: 218588-0000-0000**

**SPX Corporation  
13320 Ballantyne Corporate Place  
Charlotte, NC 28277-2706**

**Prepared By:**



**500 Bic Drive, Suite 103  
Milford, Connecticut 06461  
Telephone: 203-876-1453  
Facsimile: 203-876-1406**

**[www.trcsolutions.com](http://www.trcsolutions.com)**



## TABLE OF CONTENTS

### 1.0 Introduction

#### 1.1 Purpose

#### 1.2 Background

### 2.0 Nature of PCB Contamination

### 3.0 Cleanup Plan

#### 3.1 Bulk PCB Remediation Waste Removal and Disposal

#### 3.2 Schedule

#### 3.3 Verification

#### 3.4 Site Restoration

### 4.0 Deed Notice

### 5.0 Certification

### 6.0 Recordkeeping

Figure 1. PCB Concrete Removal – Five areas (after Delta Fig. 4)

Figure 2. Verification sample locations (after Delta Fig. 4)

## Appendices

- A. Apollo Dismantling Inc.-Waste Management Plan
- B. Delta Consultants Report "Risk-Based Remediation Plan for PCB Contaminated Concrete", December 6, 2010. Report Extract.



## 1.0 INTRODUCTION

### 1.1 PURPOSE

SPX Corporation (SPX) wishes to perform under 40 CFR 761.61 (a) (3) a *Self-implementing on-site cleanup and disposal of PCB remediation waste* at the SPX Lindberg facility located at 304 Hart Street, Watertown, WI 53094. The entire project also involves the complete demolition and remediation of the facility. SPX had received EPA's approval for a risk-based approach under 40 CFR 761.61(c). See EPA letter dated March 28, 2011.

SPX, however, no longer believes the facility is useful in its' deteriorated condition and now wishes to completely demolish the buildings and remediate the site and seeks, with the help of the City of Watertown, to find a redeveloper. Thus, SPX is seeking EPA's approval under 40 CFR 761.61(a)(3) in order to perform a *Self-implementing on-site cleanup and disposal of PCB remediation waste*.

### 1.2 BACKGROUND

Delta Consultants, Shoreview, MN has investigated the Lindberg facility for PCBs and has reported on those investigations. EPA's prior approval (March 28, 2011) was based upon that reporting. TRC has been engaged by SPX to manage/oversee the remediation and demolition. As such TRC and SPX are continuing to rely upon Delta's earlier work and their report "Risk-Based Remediation Plan for PCB-Contaminated Concrete" dated August 2, 2010 and (the subsequent modifications and revisions through December 6, 2010) it is incorporated herein. For the reader's convenience and reference the material follows this report.

The PCB contamination observed at the former Lindberg facility is believed to have been from the manufacture of electrical transformers during a period from 1953 until 1971. No spill event nor history has been identified through a historical review as well as interviews with former employees. The primary PCB contamination is of concrete flooring (within the building) and to a lesser extent a small area outside the building which is a small loading/shipping pad and adjacent soils. Notably, the PCB contamination is not at depth in the concrete flooring, thus PCB contamination is not expected in the substrate beneath any flooring. See especially the Figures in the Delta Report.

SPX, in conjunction with the facilities full demolition and remediation, will remove all Asbestos Containing Building Materials (ACM), Universal Waste (batteries, lamps-both florescent and metal-halide, mercury in electrical components, CPUs, etc.), decommission all firewater, electric, gas, water and sewer, remove all oils, lubes, etc. For the demolition all C & D waste will be disposed at the local Subtitle D (Solid Waste) landfill operated by Waste Management and located in Watertown. The ACM is to be transported and disposed at the Pheasant Run Landfill operated by Waste Management and located in Bristol, WI. Universal waste is destined for Mercury Waste Solutions in Union Grove, WI. And, the PCB concrete along with a minor amount of soil (loading pad area) would be manifested and



transported to a Subtitle C (Hazardous Waste) Landfill operated by Heritage Environmental Services located in Roachdale, IN.

## 2.0 NATURE OF PCB CONTAMINATION

The nature of the contamination is fully described and explained by Delta in their report. The sampling, the analysis, the PCB results and the graphic (figures) pattern of PCB contamination is all contained in Section 2 of their report. SPX and TRC are relying on this information for the Cleanup discussion which follows in Section 3. Please see Section 2 of the Delta report for a description of the nature of the contamination.



### 3.0 CLEAN UP PLAN

The SPX former Lindberg facility had been principally, over its long history, a manufacturer of industrial ovens, furnaces, and environmental test chambers with an associated business office activity. Early in its history the facility had also produced electrical transformers. The PCB contamination at the facility results from its manufacture of electrical transformers. The manufacturing areas were in some cases added buildings and in other cases large rooms or other functional areas within a given building-see figures. SPX will perform a self-implementing clean up resulting in PCB concentrations for the site of less than 0.74 mg/kg. This will allow unlimited use for the remaining land under EPA criteria after all remediation and demolition are completed [40 CFR 761.61(a)(4)(i)(A)]. The site, since it will be cleaned up to less than 0.74 mg/kg PCBs, will only be eligible for unlimited commercial or industrial use (not residential) under Wisconsin criteria. Thus the sites future use can only be commercial or industrial. A Deed Notice will be entered recording this environmental land use restriction. The proposed clean up includes the removal of PCB contaminated concrete, the removal of a minor quantity of PCB contaminated soils and a loading pad (only outdoor area), and the transportation and disposal of these materials to a RCRA Subtitle C facility all as more fully described below.

#### 3.1 Bulk PCB Remediation Waste Removal and Disposal

SPX intends to remove all of the concrete flooring shown on Figure 1 as PCB remediation waste. The five areas shown on the Figure will completely and conservatively remove and dispose of any concrete flooring with a PCB concentration of 50 mg/kg or above. The contractor hired by SPX, Apollo Dismantling, has mobilized to the site and is currently preparing for the demolition and remediation. At the moment Apollo and its subcontractors are removing all ACM, removing all Universal wastes, collecting all lamps and ballasts, and draining and arranging for utility shutoffs and blocks. Once this work is completed Apollo had planned to cut out and remove all of the PCB concrete for Title C Landfill disposal. See schedule below.

The concrete removal will be in all cases to full floor depth. In addition, SPX proposes to remove to the next core location (still locatable) where a measured result is less than 50 mg/kg content. Thus existing measured values and full depth floor removal ensures the cleanup objective is met. The removed flooring will then be manifested, transported and disposed at the Subtitle C landfill operated by Heritage Environmental Services located in Roachdale, Indiana.

Remaining flooring will then be removed from all areas (rooms and/or buildings). The material will be sized and placed in a single on site pile for further use on site, if possible. Prior to any on-site use the pile will be sampled and analyzed to ensure that the material is less than 0.74 mg/kg PCB content. If less than, the material is candidate material for onsite use to fill any basement voids and grade the site after the demolition. Should the any pile material test greater than 0.74 mg/kg it will not be used onsite but will be disposed into a Subtitle D landfill, either for temporary cover or as fill. Thus any PCB concrete



greater than 50 mg/kg (and minor soils quantity) will be disposed at a Subtitle C (Hazardous Waste) facility; any PCB concrete greater than 0.74 mg/kg will be disposed in a Subtitle D (Solid Waste) landfill facility; and, any PCB concrete less than 0.74 mg/kg may be retained for use to fill basement voids onsite and grading-or if an excessive quantity exists, may also be disposed in the same Subtitle D landfill facility.

### 3.2 SCHEDULE

The schedule is as follows:

ACM removal, 24 Oct-23 Dec/14

PCB remediation waste removal, 15 Jan-28 Feb/15

Lights/ballasts/U waste, 17 Nov-15 Dec/14

Demolition, 5 Jan-28 Feb/15

Site Restoration, Mar-Apr/15

### 3.3 Verification

Verification sampling will be performed under all five PCB remediation waste removal areas. See Figure 2 for proposed sample locations. ASTM Method D2974 will be used for moisture content and EPA Method 8082 will be used for sample analysis. Reporting will be for the seven congeners required by WI DNR and total PCB. The outdoor excavation will be sampled with 2-sidewalls samples and a bottom invert sample. Any concrete pile proposed for onsite reuse (filling and grading) will be sampled with 6 samples, composited to 2 for analysis.

### 3.4 Site Restoration

After completion of all the demolition and remediation activities the site will be restored. The front side walk on Hart Street will remain. The voids of former basement areas will be filled with the concrete from the less than 0.74 mg/kg pile (assuming it has been verified as described herein). After the voids are filled fresh stone will be imported to cover the graded concrete areas. The site will be somewhat crowned to allow that no ponding should occur over time. The property will then be idle until redevelopment can be planned and implemented.

### 4.0 Deed Notice

SPX Corporation will prepare and have entered a Deed Notice which will limit the property uses to commercial and/or industrial only. The use of the property for residential purposes will be prohibited. Full-time commercial or industrial uses will be allowed since the clean up to less than 0.74 mg/kg PCBs meet the criteria for both EPA and WI DNR.

Revised 12/19/2014



## 5.0 Certification

SPX Corporation as the Owner and Operator and Successor in Interest of the former SPX Lindberg site hereby certifies and notifies that the site located at:

304 Hart Street, City of Watertown, County of Jefferson, Wisconsin (The former Lindberg facility)

(SPX) is proposing a "self-implementing on-site cleanup and disposal of PCB remediation waste", and as such SPX has engaged Apollo Dismantling Services, LLC of Niagara Falls, NY to perform the remediation and proper disposal of the site PCB remediation waste, further


a complete package of all PCB sampling, analysis, results, maps, and other PCB related documents will be available on site for EPA's inspection anytime throughout the duration of the project. All information will be available electronically in the Apollo field construction trailer located at the site.

## 6.0 RECORDKEEPING


A file containing all sampling, analysis, results, graphic depictions of results, shipping and manifesting documents including weight tickets and summaries will be created. Several electronic copies of the record compilation will be made. An electronic copy will be forwarded to USEPA Region 5 PCB Coordinator and to WI DNR PCB Section.

Since this is a cleanup to less than 0.74 mg/kg PCB no further environmental actions are anticipated under 40 CFR 761.61.











Report & Documents - Same As Nov 2014  
Herein AFTER



**Waste Management Plan**  
November 2014

**SPX - Lindberg**  
**304 Hart Street**  
**Watertown, WI 53094**

**Prepared for:**

**SPX**


13320 Ballantyne Corporate Place  
Charlotte, NC 28277

**Prepared by:**

**APOLLO DISMANTLING**

4511 Hyde Park Blvd.  
2<sup>nd</sup> Floor  
Niagara Falls, NY 14305





**LEGEND**

0.718  
⊗ PREVIOUS PCB SOIL SAMPLE LOCATION & CONCENTRATION (mg/kg)  
☒ TEST PIT LOCATION  
● GEOPROBE® SOIL BORING (YELLOW OUTLINED SOIL BORING ID DEPICTS A NON-DETECT RESULT)

B-1A (0.11) SAMPLE RESULTS DO NOT EXCEED THE RESIDENTIAL CLEANUP STANDARD OF 0.221 mg/kg  
B-10A (110) SAMPLE RESULTS EXCEED THE RESIDENTIAL CLEANUP STANDARD OF 0.221 mg/kg  
B-10A (0.22) SAMPLE RESULTS EQUAL THE RESIDENTIAL CLEANUP STANDARD OF 0.221 mg/kg  
(0.19) SAMPLE COLLECTED BY MARK KNIGHT, CONSULTANT FOR MR. **nonre**  
15.11

**NOTES**

1. BASE MAP IMAGERY FROM GOOGLE EARTH PRO & PARTNERS, 2014.  
2. LABORATORY RESULTS ARE LOCATED ON TABLE 1 FOR THE TEST PITS AND GEOPROBE® BORINGS.  
3. BORINGS B-1 THROUGH B-33 WERE COMPLETED ON 11/05/2015.  
4. BORINGS B-34 THROUGH B-41 WERE COMPLETED ON 01/08/2016.  
5. TEST PITS WERE COMPLETED ON 11/02/2015.

0 40 80 Feet  
1" = 40'  
1:480

DRAFT

PROJECT: SPX - LINDBERGH/MPH  
WATERTOWN, WISCONSIN

SHEET TITLE: SOIL BORING & SAMPLE LOCATION RESULTS

DRAWN BY: SUEMNICHT R	SCALE: 1: 480	PROJ. NO. 218558
CHECKED BY:	DATE PRINTED:	FILE NO. 218588-006.mxd
APPROVED BY:		FIGURE 2
DATE: JANUARY 2016		

708 Heartland Trail, Suite 3000  
Madison, WI 53717  
Phone: 608.826.3600  
www.trcsolutions.com







## Nemani, Nate

---

**From:** Ackerman, Jeffrey A - DNR <Jeffrey.Ackerman@wisconsin.gov>  
**Sent:** Friday, January 29, 2016 2:15 PM  
**To:** Nemani, Nate  
**Cc:** Edelstein, Gary A - DNR  
**Subject:** FW: SPX Watertown  
**Attachments:** SPX BoringsfigJan20results218588-006 (005).pdf; SPX BoringsfigJan20218588-008 (003).pdf; 20160129135632914.pdf

Hi Nate,

Here is the latest for SPX (what we call Lindberg/MPH in our database). We don't have a report yet and these results are draft.

I am also including our notification form to close the loop on that.

Let me know when you would like to talk. Next week my schedule is open Tuesday and Wednesday and in the afternoon of Thursday and Friday.

Jeff

**We are committed to service excellence.**

Visit our survey at <http://dnr.wi.gov/customersurvey> to evaluate how I did.

Jeff Ackerman  
608-275-3323  
[jeff.ackerman@wisconsin.gov](mailto:jeff.ackerman@wisconsin.gov)

---

**From:** McNichol, David [mailto:DMcNichol@trcsolutions.com]  
**Sent:** Thursday, January 21, 2016 10:31 AM  
**To:** Ackerman, Jeffrey A - DNR  
**Subject:** SPX Watertown

Jeff Hi

I will try to call you a little later to discuss the attached. Note that these are draft and as such for discussion only until data is validated and GPS data confirmed.

Thanks

Best  
Dave

Dave McNichol  
Senior Consultant



500 Bic Drive, Ste. 103, Milford, CT 06461  
T: 203.876.1453 | F: 203.876.1486 | C: 203.856.8388

[dmcnichol@trcsolutions.com](mailto:dmcnichol@trcsolutions.com)







**Notice #1 – DNR Notification to EPA Form for PCB Contamination per OCP MOA**

For notification of EPA new discovered PCB sites entered onto BRRTS. EPA will also track these cases. DNR agrees to provide the following in electronic form:

BRRTS#	02-28-555133
Start Date	02/16/2010
Site Name	LINDBERG/MPH FACILITY
Site Address	304 HART ST, Watertown, WI
County	Jefferson
DNR PM Name	Jeff Ackerman
DNR PM Phone#	(608) 275-3323
PCB Site MOA Type	Uncertain
Impact	Soil

DNR will identify PCBs as being a substance type in BRRTS for these sites.

A copy of DNR's RP notification letter should be converted to a pdf file and accompany this form.

Upon completion of this form by DNR, please email this form and a pdf of the RP letter to the EPA Region 5 PCB coordinator with an email cc to the DNR RR Bureau PCB Contact.

Add BRRTS Action Code 99 with the date and comment stating "OCP PCB Notice #1, Notification of a PCB Contamination Site sent to EPA"

Upon receipt of the form by EPA, EPA will assign a Region 5 contact to the case and notify the DNR PM and the DNR RR Bureau PCB contact. The DNR PM should enter the name of the EPA contact into BRRTS for the site.









**LEGEND**

- PROPOSED GEOPROBE® SOIL BORING LOCATION
- GEOPROBE® SOIL BORING

**NOTES**

- BASE MAP IMAGERY FROM GOOGLE EARTH PRO & PARTNERS, 2014.
- LABORATORY RESULTS ARE LOCATED ON TABLE 1 FOR THE TEST PITS AND GEOPROBE® BORINGS.
- BORINGS B-1 THROUGH B-33 WERE COMPLETED ON 11/05/2015.
- BORINGS B-34 THROUGH B-41 WERE COMPLETED ON 01/08/1991.
- TEST PITS WERE COMPLETED ON 11/02/2015.

04080Feet

1" = 40'  
1:480

DRAFT


PROJECT: SPX - LINDBERGH/MPH WATERTOWN, WISCONSIN		
SHEET TITLE: PROPOSED SOIL BORINGS		
DRAWN BY: SUEMNICHT R	SCALE: 1:480	PROJ. NO. 218558
CHECKED BY:		FILE NO. 218588-008.mxd
APPROVED BY:	DATE PRINTED:	FIGURE 1
DATE: JANUARY 2016		

708 Heartland Trail, Suite 3000  
Madison, WI 53717  
Phone: 608.826.3600  
www.trcsolutions.com









October 26, 2016

Walter Galacki  
Global Director, Environmental, Health & Safety  
SPX Corporation  
13320-A Ballantyne Corporate Place  
Charlotte, North Carolina 28277

Subject: Review of Draft Documents for the Lindberg/MPH Facility Cleanup Case (aka SPX)  
304 Hart Street and Neighboring Properties, Watertown, WI  
DNR Case # 02-28-555133

Dear Mr. Galacki:

Thank you for having TRC send in the draft documents for the investigation and cleanup at the former Lindberg/MPH facility in Watertown, Wisconsin. The three draft documents include:

1. "Remediation Action Investigation & Design Report – SPX Corporation, Inc. – 304 Hart Street, Watertown, Wisconsin 53094 – September 2016"
2. "Remediation Action Investigation & Design Report for **nonresponsive**, Watertown, Wisconsin, 53904"
3. "Soils Management Plan for Remediation Actions Regarding PCB Contamination of Soils for the **nonre** Properties and the SPX Corporation Property in Watertown, Wisconsin – September 2016"

The concepts presented in the reports and plans appear reasonable, but you will need to provide additional information to assure that the final submittal(s) contain the necessary details and comply with the cleanup rules. Additional EPA involvement may also be necessary depending on the regulatory path you wish to pursue.

The extent of contamination must be more thoroughly evaluated to assure that there are no direct contact soil exceedences on the west side of South 3<sup>rd</sup> Street. TRC has not identified a source of the PCB contamination and one sample just east of 3<sup>rd</sup> Street (G-1) showed PCBs in excess of the residential direct contact standard. The additional sampling will assure that the PCB issue is fully addressed. Sampling prior to the excavation will also be useful in evaluating the effectiveness of dust control measures used during remedial excavations. If fugitive dust becomes an issue we may require additional soil sampling in the neighboring areas following the excavations.

We suggest that SPX consider doing public outreach prior to the remediation. The project has generated significant public interest and uncertainty sometimes heightens public concerns. Providing the public with information on the project could allay some of these concerns. The State and local health departments have expressed interest in doing public outreach for this case, and they could offer assistance.

The findings of PCBs above 50 parts per million means the site may also be regulated by the Environmental Protection Agency (EPA). If you wish for a "coordinated approval process", which allows Wisconsin to take the lead on the cleanup under the State's authority, you will need to make a request to the EPA in accordance with the requirements of 40 CFR 761.77(1)(1). For additional information on the regulatory framework and your options, please review our guidance document RR-786, "PCB Remediation in Wisconsin Under the One Cleanup Program Memorandum of Understanding, November 2014" at <http://dnr.wi.gov/files/pdf/pubs/rr/tr786.pdf>.



The Wisconsin cleanup code requirements are contained within the NR 700 rule series of the Wisconsin Administrative Code. I understand that TRC is aware of these rules and has access to them. For your reference and as a matter of disclosure, the NR 700 code and other relevant cleanup rules, including the Spill Law (Wis. Stat. ch. 292), can be accessed at <http://dnr.wi.gov/topic/brownfields/laws.html>. Several chapters and sections of the cleanup rules are referenced in this letter.

We view this case as one discharge site. As such, the investigation documentation should be submitted as one report. Parsing the data into two reports makes the information harder to understand and this type of presentation does not appear to be in compliance with the code requirements. TRC should create a comprehensive document that includes all of the site data and supporting documentation.

The final report and remediation plan must include the professional certification and sign-off(s) required under Wis. Adm. Code Ch. NR 712.

The data presentation needs to better explain the extent and distribution of the contaminants at the site. TRC should review the Wis. Adm. Code Ch. NR 716 requirements. Some examples of improvements that will aid in a better understanding of the site and the appropriateness of the proposed remedial action:

- A site map that meets the code requirements, and most notably shows the buried utilities.
- Geologic cross sections that show the fill, native soil type(s), and depth and extent of contamination.
- Soil data tables showing the sampling dates and specify the PCB arochlor and relevant standard(s).
- Isoconcentration maps that show the distribution of contamination, including the depths and concentrations detected at all samples, including the no detection results.
- The soil origins should be included on the test pit logs.

The remedial action plan documents do not meet the requirements of Wis. Adm. Code Ch. 724. Some examples:

- The information required under sec. 724.05 (2) (e) should be included.
- Calculations for the soil volumes should be shown and the results should be consistently referenced.
- Maps showing the proposed excavations super-imposed on the isoconcentration maps of soil contamination should be presented.
- Cross-sections showing the proposed excavations relative to the contamination should be presented.
- A better explanation of the soil confirmation sampling should be presented; depths, locations, and frequency relative to area or volume of excavation.
- Include a contingency plan for possible problems, such as water collecting in the excavation(s) or the possibility of a significant amount of fugitive dust.
- A contact for questions on the project should be included.
- The remedial action plan and soil management plan(s) should be stand-alone documents or they can be combined with the site investigation report. The reader should not need to reference figures contained in a separate document.

Some additional considerations for the final investigation plan and remedial action plans:


- Avoid storage of higher level (>50 ppm) PCB contaminated soil at the site, or provide justification as to why it should be temporarily stockpiled at the site.
- List "Arochlor 1260" as the contaminant rather than total PCBs, and note the default direct contact cleanup goals for Arochlor 1260 are 0.731 ppm industrial uses, and 0.216 ppm for non-industrial uses.
- The proposed soil volumes and areas of excavation should be consistent across the documents. For instance, compare the soil volumes in section 2.2 of the soil management plan with figure 5 of the site investigation report.



- The discussion for fill in the site investigation report at Hart street references "clean fill" for backfill, whereas the soil management plan includes re-use of impacted soil from the **nonre** properties.
- Was there any soil removed from beneath the building slab? If so, this should be documented in compliance with the Wis. Adm. Code ch. NR 724 requirements.
- A continuing obligation will be needed for the Hart Street location; the site will need to be kept in industrial use due to the higher cleanup standard.

Please have TRC submit the final investigation and remedial action plan document(s) at their earliest convenience. If you would like to discuss this letter please let me know.

Sincerely,



Jeff Ackerman  
Hydrogeologist  
(608) 275-3323  
[jeff.ackerman@wi.gov](mailto:jeff.ackerman@wi.gov)

cc: Dave McNichol, TRC-Connecticut  
Rob Thibodeaux, Wisconsin DHS  
Carol Quest, Watertown Dept of Public Health  
**nonresponsiv**







## Nemani, Nate

---

**From:** Ackerman, Jeffrey A - DNR <Jeffrey.Ackerman@wisconsin.gov>  
**Sent:** Friday, October 07, 2016 4:04 PM  
**To:** Nemani, Nate; Ramanauskas, Peter  
**Cc:** Edelstein, Gary A - DNR  
**Subject:** SPX (aka Lindberg MPH) - Watertown, WI - PCBs > 50 ppm  
**Attachments:** lindberg mph spx rp letter.pdf

Hi Nate and Peter,

We have talked about this site and I have shared data with you. Recently submitted reports show greater than 50 ppm PCBs in soil at the cleanup site to the west of the former building. The reports are available through our website at

<http://dnr.wi.gov/botw/GetActivityDetail.do?adn=0228555133&siteId=1553200&crumb=1&search=b>

If you need hard copies of these three documents, please contact Dave McNichol at TRC:

Dave McNichol  
Senior Consultant  
500 Bic Drive, Ste. 103, Milford, CT 06461  
T: 203.876.1453 | F: 203.876.1486 | C: 203.856.8388  
[dmcnichol@trcsolutions.com](mailto:dmcnichol@trcsolutions.com)

I can't find an initial (formal) notification to EPA and I want to close the loop on the DNR/EPA MOA requirements. Here is the information required in the notification form.

### **DNR Notification to EPA Form for PCB Contamination per OCP MOA**

BRRTS #: 02-28-555133  
Start Date: 2010-02-16  
Site Name: Lindberg MPH  
Site Address: 304 Hart St, Watertown  
County: Jefferson County, Wisconsin  
DNR PM Name: Jeff Ackerman  
DNR PM Phone #: 608-275-3323  
DNR PM Email: [jeff.ackerman@wi.gov](mailto:jeff.ackerman@wi.gov)  
PCB Site MOA Type if known (A, B or C – see guidance): possible change to Type C site  
Impact (Soil, GW, etc. if received): soil

Per the form requirements, I am also attaching a copy of our March 2010 responsible party letter.

I will inform the responsible party and consultant that they will need to request the site go into the coordinated approval process, if that is their preferred regulatory route.

Please let me know if you have questions.

**We are committed to service excellence.**

Visit our survey at <http://dnr.wi.gov/customersurvey> to evaluate how I did.



Jeff Ackerman

Hydrogeologist – Bureau for Remediation and Redevelopment/Environmental Management Division

Wisconsin Department of Natural Resources

3911 Fish Hatchery Road, Fitchburg, WI 53711

Phone: 608-275-3323


[jeff.ackerman@wisconsin.gov](mailto:jeff.ackerman@wisconsin.gov)



[dnr.wi.gov](http://dnr.wi.gov)







## State of Wisconsin \ DEPARTMENT OF NATURAL RESOURCES

Jim Doyle, Governor  
Matthew Frank, Secretary  
Lloyd L. Eagan, Regional Director

South Central Region Headquarters  
3911 Fish Hatchery Road  
Fitchburg, Wisconsin 53711-5397  
Telephone 608-275-3266  
FAX 608-275-3338  
TDD 608-275-3231

March 25, 2010

BRRTS # 02-28-555133

Mr. Dan McGrade  
SPX Corporation  
13515 Ballantyne Corporate Place  
Charlotte NC 28277

**SUBJECT: Reported Contamination at: Lindberg MPH Facility, 304 Hart St. Watertown WI**

Dear Mr. McGrade:

On February 16, 2010 Karen Thole representing Delta Consultants notified the Department of Natural Resources that groundwater contamination via VOC's had been detected at the site listed above. Based on the information submitted to the Wisconsin Department of Natural Resources (WDNR), we believe you are responsible for restoring the environment at the referenced site under Section 292, Wisconsin Stats., known as the hazardous substances spills law.

This letter describes your legal responsibilities, explains what you need to do to investigate and clean up the contamination, and provides you with information about cleanups, environmental consultants, possible financial assistance, and working cooperatively with the Departments of Natural Resources and Commerce.

### **Legal Responsibilities:**

Your legal responsibilities are defined both in statute and in administrative codes. The hazardous substances spill law, Section 292.11 (3) Wisconsin Stats, states:

- **RESPONSIBILITY.** A person who possesses or controls a hazardous substance which is discharged or who causes the discharge of a hazardous substance shall take the actions necessary to restore the environment to the extent practicable and minimize the harmful effects from the discharge to the air, lands, or waters of the state.

Wisconsin Administrative Code chapters NR 700 through NR 749 establish requirements for emergency and interim actions, public information, site investigations, design and operation of remedial action systems, and case closure. Chapter NR 708 includes provisions for immediate actions in response to limited contamination. Wisconsin Administrative Code chapter NR 140 establishes groundwater standards for contaminants that reach groundwater.

### **Steps to Take:**

The longer contamination is left in the environment the farther it can spread and the more it may cost to clean up. Quick action may lessen damage to your property and neighboring properties and reduce your costs in investigating and cleaning up the contamination. To ensure that your cleanup complies with Wisconsin's laws and administrative codes, you should hire a professional environmental consultant who understands what needs to be done. These are the first three steps to take:

1. Within the next 30 days, you must submit written verification (such as a letter from the consultant) that you have hired an environmental consultant.



*Quality Natural Resources Management  
Through Excellent Customer Service*





2. Within the next 60 days, your consultant must submit a workplan and schedule for the investigation. The consultant must follow the DNR administrative codes and technical guidance documents.

Once an investigation has established the type and severity of contamination involved at your site, your consultant will be able to determine whether the Department of Commerce or the Department of Natural Resources has authority over the case. The decision will be reviewed by agency staff, and you will be notified by mail if the case is being transferred to Commerce. In general, cases involving petroleum products that have leaked from either above ground or underground storage systems will be reviewed by the Commerce, unless high risk criteria are involved.

3. Please inform the appropriate agency of what is being done at your site. If the site meets criteria for a "simple site", progress reports must be submitted semi-annually, beginning 6 months from the initial notification date. If the site meets criteria for a "complex site", a complete site investigation report and a draft remedial options report must be submitted within 30 days of completion. In addition, you or your consultant must provide a brief report at least every 90 days. Quarterly reports need only include one or two pages of text, plus any relevant maps and tables. Should conditions at your site warrant, we may require more frequent contacts.

If you want a formal response from the agency on a specific submittal, please be aware that a review fee is required in accordance with s. NR 749, Wis. Adm. Code. If a fee is not submitted with your reports, you should proceed under the advice of your consultant to complete the site investigation to maintain your compliance with the spills law and chs. NR 700 through NR 749. **Do not delay the investigation of your site by waiting for an agency response.** We have provided detailed technical guidance to environmental consultants. Your consultant is expected to know our technical procedures and administrative codes and should be able to answer your questions on meeting cleanup requirements."

Unless you are notified that your case has been transferred to Commerce, all correspondence regarding this site should be sent to:

Jeff Ackerman  
Remediation and Redevelopment Program  
Wisconsin Department of Natural Resources  
3911 Fish Hatchery Road  
Madison, WI 53711

Unless otherwise requested, please send only one copy of plans and reports. To speed processing, correspondence should reference the BRTS and FID numbers (if assigned) shown at the top of this letter.

**Information for Site Owners:**


Information to help you select a consultant, and materials on controlling costs, understanding the cleanup process, and choosing a site cleanup method are enclosed. For information on obtaining limited liability under Section 292.15, Wisconsin Stats., please see our website at <http://www.dnr.state.wi.us/org/aw/rr/liability>.

**Financial Assistance:**

Reimbursement from the Petroleum Environmental Cleanup Fund (PECFA) is available for the costs of cleaning up contamination from eligible petroleum storage tanks. Please refer to the enclosed information sheet entitled *Site Remediation Using PECFA* for more information on eligibility and regulations for this program.

Thank you for your cooperation.

Sincerely,


  
Jeff Ackerman  
Telephone: (608) 275-3323  
Enclosures

Cc → File

Karen Thole Delta Consultants




UNITED STATES POSTAL SERVICE



First-Class Mail  
Postage & Fees Paid  
USPS  
Permit No. G-10

• Sender: Please print your name, address, and ZIP+4 in this box •

Nate Nemani  
US EPA  
77 West Jackson Boulevard LU-9J  
Chicago, IL 60604





**SENDER: COMPLETE THIS SECTION**

- Complete items 1, 2, and 3. Also complete item 4 if Restricted Delivery is desired.
- Print your name and address on the reverse so that we can return the card to you.
- Attach this card to the back of the mailpiece or on the front if space permits.

1. Article Addressed to:

Mr. Daniel McGrade  
Environmental Director  
SPX Corporation  
13515 Ballantyne Corporate Place  
Charlotte, North Carolina 28277

2. Article Number

(Transfer from service label)

7001 0320 0006 0192 5183

PS Form 3811, March 2001

**COMPLETE THIS SECTION ON DELIVERY**

A. Received by (Please Print Clearly)

B. Date of Delivery

*Robert F. Kelly*

03/13/01

C. Signature

*Robert F. Kelly*



☐ Agent

☒ Addressee

D. Is delivery address different from item 1?

☐ Yes

If YES, enter delivery address below:

☐ No

3. Service Type

☒ Certified Mail

☐ Express Mail

☐ Registered

☒ Return Receipt for Merchandise

☐ Insured Mail

☐ C.O.D.

4. Restricted Delivery? (Extra Fee)

☐ Yes

Domestic Return Receipt

102595-01-M-1424





UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION 5  
77 WEST JACKSON BOULEVARD  
CHICAGO, IL 60604-3590

MAR 28 2011

REPLY TO THE ATTENTION OF:

L-8J

**CERTIFIED MAIL:**  
**RETURN RECEIPT REQUESTED**

Mr. Daniel McGrade  
Environmental Director  
SPX Corporation  
13515 Ballantyne Corporate Place  
Charlotte, North Carolina 28277

Dear Mr. McGrade:

The U.S. Environmental Protection Agency, Region 5 has reviewed the Risk-Based Remediation Plan (Plan) dated August 11, 2010 and the subsequently revised plan of December 6, 2010, prepared and submitted by Delta Consultants of Shoreview, Minnesota, on behalf of SPX Corporation, for the SPX Lindberg facility (SPX) in Watertown, Wisconsin. EPA hereby approves the Plan subject to the attached conditions.

In summary, the Plan calls for a Risk-Based Remediation/clean-up and disposal of Polychlorinated Biphenyl (PCB) impacted concrete at SPX's subject manufacturing facility in Watertown, Wisconsin in accordance with the EPA Toxic Substance Control Act (TSCA) PCB regulations 40 CFR§ 761.61(c). Industrial land use restrictions shall apply to the property for all future uses.

Based on facility-wide sampling it was determined that approximately 20,650 square feet of concrete contains PCB at concentrations greater than 10 mg/kg. The following remediation methods are being proposed for the facility to address the areas with PCB concentrations greater than 10 mg/kg (proposed risk-based clean up level) conditioned upon its continued industrial use and limited accessibility.

- a) Bulk PCB Remediation Waste Removal and off-site disposal of a 700 square foot concrete pad in the rail spur loading area is proposed. In addition, bulk PCB Remediation Waste Removal and off-site disposal of approximately 800 square feet of PCB contaminated concrete flooring located at eight (8) non-contiguous locations each approximately 10 feet by 10 feet is also in the Plan.
- b) Continued Use Authorization management as per 40 CFR § 761.30(p) of 19,150 square feet of PCB contaminated bare concrete. The flooring shall be divided into two distinct areas based on the surface condition of the concrete. The first area (12,150 square feet) which is the bare concrete portion shall undergo cleaning per Subpart S of the regulations followed by two coats of epoxy. The second area




(7,000 square feet), the portion presently covered with a white epoxy coating, shall be subjected to a superficial cleaning followed by two coats of epoxy.

This approval of the Plan, as described above, is granted by EPA in accordance with the federal PCB regulations codified under 40 CFR§761.61(c), under which the Regional Administrator may approve a Risk-Based disposal approval application, if it is found that the method will not pose an unreasonable risk of injury to human health or the environment. The Regional Administrator has redelegated this approval authority to the Director of Land and Chemicals Division. PCB remediation and clean-up activities will need to be conducted in accordance with the report dated August 11, 2010 and subsequently revised per the e-mail and its attachment dated December 6, 2010.

SPX is responsible for ensuring continued compliance with all applicable provisions of the Toxic Substances Control Act (TSCA), the federal PCB regulations and the Conditions of this approval, attached herewith. All conditions of this approval and other applicable requirements of TSCA and its regulations will continue to apply to the site after any transfer in ownership.

Please do not hesitate to call Nate Nemani, of my staff, at (312) 886-3224, if you have any questions regarding this approval.

Sincerely,

A handwritten signature in black ink, appearing to read "Richard C. Karl".

Richard C Karl  
Acting Director  
Land and Chemicals Division

Enclosure

cc: Jeff Ackerman, Wisconsin Department of Natural Resources (WDNR)  
Karen Thole, Delta Consultants



## **APPROVAL CONDITIONS**

### **A. Authorized Remedial Action**

1. SPX is authorized to clean-up and dispose of PCB remediation waste at its facility in Watertown, Wisconsin facility located at 304 Hart Street (Site) according to the procedures described in the August 11, 2010 report titled Risk-Based Remediation Plan for PCB Contaminated Concrete and the subsequent revisions described in the December 6, 2010 email and its attachments. It is noted that the source of the PCB contaminated does not exist any longer. The following requirements need to be adhered to:

- a) **Bulk PCB Remediation Waste Removal and Disposal:**

SPX will remove a 16 foot by 43 foot concrete pad located in the rail spur loading area. In addition to the rail spur loading area, eight (8) non-contiguous concrete sample locations will undergo similar removal and disposal. Given the limited area and vertical extent of PCBs in these eight locations, SPX will cut out and remove the entire thickness of a 10 foot by 10 foot concrete floor surrounding each sample location where the concentrations exceeded 10 mg/kg. The disposal of the material will be at a TSCA permitted Landfill in accordance with regulations under 40 CFR§761.61(a)(5)(i)(B)(2).

- b) **Continued Use Authorization:**

In accordance with requirements set forth in 40 CFR 761.30(p), porous surfaces contaminated by an old liquid PCB spill where the surface concentration is greater than 10 micrograms per 100 square centimeters are subjected to the continued use provisions, which state that (i) the accessible porous surfaces must be cleaned and completely covered with two solvent resistant and water repellant coatings of contrasting colors and (ii) a visible PCB mark be placed in a visible location. As described earlier, the area where the surface concentrations exceeded 10 micrograms per 100 square centimeters (12,150 square feet) shall be subjected to a more rigorous cleaning than the areas that exhibited concentrations less than or equal to 10 micrograms per 100 square centimeters (7,000 square feet).

In summary, the remediation and clean-up at the SPX facility shall be as per the procedures outlined in the revised section 3.0 titled **Clean-up Plan** detailed in the attachment to the December 6, 2010 e-mail from Ms. Karen Thole of Delta Consultants. The original plan was detailed in the report titled **Risk-Based Remediation for PCB-Contaminated Concrete**, dated August 11, 2010.



c) **Property Use and Restrictions and Notice:**

Within 60 days of completion of the above approved removal activities, SPX will record, in accordance with state law and 40 CFR 761.61(a)(8)(i), a notation to the deed for the Facility. A **draft** of the Deed Notice shall be submitted to EPA for review prior to its official filing with the appropriate local governmental body. A written certification indicating that the deed restriction has been filed will need to be submitted to the EPA Regional Administrator.

**B. Inspection, Maintenance and Monitoring**

Plans for the Long Term Management of the PCB affected concrete shall be put in place for implementation as needed. An Operations and Maintenance Plan shall be developed for minimizing human exposures. This shall include training of workers for inspecting the encapsulant for wear and damage, procedures for repairing the encapsulant as needed and a safety plan for workers in case repair of the area is required. The management plan shall also include addressing the ultimate removal and disposal of PCB contaminated concrete and soil remaining beneath the encapsulant in the event of building demolition or renovation. Any concrete containing PCB concentrations >1ppm must be disposed of per 40 CFR§761.61.

**C. Change of Ownership**

1. At least 45 days before conveying, in any manner, ownership or responsibility of the Facility or underlying property SPX will notify EPA Region 5, of its intent to convey such ownership or responsibility. Such notice will include the date of the intended conveyance, and the name, address, and phone number of the intended new owner or responsible person. If the conveyance is being made to a corporate entity, this notice will also include the name of a contact person.
2. At least 30 days before such conveyance, SPX will submit to EPA, Region 5, a notarized affidavit signed by the intended new owner or responsible person who states that such person will abide by the provisions of this Risk-Based Approval granted to SPX for this Facility.

**D. Record-keeping and Reporting**

1. SPX will maintain all records and documents as required by 40 CFR Part 761.
2. SPX will submit a Closure Certification Report to EPA and WDNR within 90 days of completion of the activities described under this Approval. At a minimum, the report will include: a discussion of project activities, as-built specifications, sampling analytical results, copies of the accompanying analytical chains of custody, quality control/quality assurance checks, an estimate of the quantity of PCBs removed and disposed of off-site, and copies of manifests.





**UNITED STATES ENVIRONMENTAL PROTECTION AGENCY**

**Region 1**

**5 Post Office Square, Suite 100**

**Boston, MA 02109-3912**

**SELF-IMPLEMENTING CLEANUP AND DISPOSAL § 761.61(a)(3) CHECKLIST**

**I. Cleanup and Disposal Notification to EPA with the following:**

- ☐ Cover letter stating purpose of the submission and signed by the Site owner or operator, or by the party responsible for conducting the cleanup, such as a former Site owner.
- ☐ A plan which includes the following information:
  - ☐ Site background and history. This should include a discussion of past activities (e.g. use of PCBs and/or PCB equipment, storage, manufacturing, etc), site ownership, and current or proposed site uses. This section should also include information on any cleanups/remediations that have occurred at the Site.
  - ☐ The nature of the contamination, including the kinds of materials contaminated (§ 761.61(a)(3)(i)(A)).
  - ☐ A summary of the standard operating procedures (SOPs) employed during characterization of the Site, including a table or cleanup Site map showing PCB concentrations measured in the pre-cleanup characterization samples. The SOPs must include information on the field sample collection procedures and field and/or laboratory extraction and analytical procedures (§ 761.61(a)(3)(i)(B)).
  - ☐ A Site map showing the PCB sampling locations cross referenced to the sample identification numbers provided as part of the characterization information. The extent of the identified PCB contaminated area(s) must be clearly identified (§ 761.61(a)(3)(i)(C)).



- ☐ Copies of the laboratory analytical reports of the characterization sampling, including field and laboratory quality assurance/quality control samples, should be provided to document the extraction/analytical dates and methods and laboratory QC (§ 761.61(a)(3)(i)(C)).

*If extensive, the laboratory analytical reports may be provided on a CD-ROM.*

- ☐ A cleanup plan for the Site, including the proposed disposal technology and approach, and a cleanup schedule. ***The plan must include contingency plans in the event that higher PCB concentrations and/or a wider distribution of PCBs are identified during the cleanup*** (§ 761.61(a)(3)(i)(D)).
- ☐ A written certification, signed by the owner of the property where the cleanup site is located and the party conducting the cleanup, that all sampling plans, sample collection procedures, sample preparation procedures, extraction procedures, and instrumental/chemical analysis procedures used to assess or characterize the PCB contamination at the cleanup site, are on file at the location designated in the certificate, and are available for EPA inspection (§ 761.61(a)(3)(i)(E)).
- ☐ Subpart Q alternative method: If an alternative method of extraction and/or analysis is/will be used, the certification shall include a statement to this fact and that a comparison study which meets or exceeds the requirements of Subpart Q has been completed prior to the verification sampling. In the event that the alternative extraction and/or analytical method was previously validated under Subpart Q using materials from other projects, the laboratory must provide a certification that the sample types used during that comparison study are similar to (e.g., % organic content, grain size, etc) the sample types that will be cleaned up under the Notification. A copy of the Subpart Q comparison study should be included in the Notification (§ 761.61(a)(3)(i)(E)).
- ☐ QA/QC plan for documenting that the cleanup levels have been achieved (e.g. confirmatory sampling/analysis QA/QC). The QA/QC plan should at a minimum include information on the types/numbers of samples; extraction/analytical methods; MS/MSDs (both frequency and acceptance criteria), etc. The QA/QC plan should also discuss data validation.



- ☐ In the event that the party conducting the cleanup is not the Site owner (for example, the party could be a previous Site owner), EPA will require documentation that the party conducting the cleanup legally has the authority to access the Site and to conduct the proposed PCB activities. This documentation for example may be in the form of a Site Access Agreement stating this fact or perhaps in a lease agreement or a property transfer agreement.
- ☐ If a cleanup will involve the use of a cap, the cap design specifications and a cross-section showing the design should be provided. Please insure that it is clear where the cap will be used. *Please note: the use of a cap will require a deed notation documenting this fact and the limitations on the use of the Site (§§ 761.61(a)(7) and (8)).*

## II. Important Considerations:

This checklist provides only a summary of the information that is specified under § 761.61(a)(3), is for reference only, and is not intended to replace the requirements of the PCB regulations.

Region 1 requires that the SOPs and QA/QC information be submitted as part of the Notification.

The Notification may include any additional information that supports the proposed cleanup, such as information regarding state regulations, community involvement (especially for schools), and environmental justice communities. In addition, any documentation that has been developed for a state regulatory agency, such as a remedial investigation report, may be submitted to support the pertinent required documentation in lieu of generating a new document.

The 30-day default timeframe for EPA review of a Self-Implementing PCB Cleanup and Disposal Notification (§ 761.61(a)(3)(ii)) does not apply if the proposed PCB plan does not follow the prescriptive cleanup and disposal procedures and provisions specified under § 761.61(a).







## Nemani, Nate

---

**From:** McNichol, David <DMcNichol@trcsolutions.com>  
**Sent:** Friday, January 02, 2015 10:30 AM  
**To:** Nemani, Nate  
**Cc:** Galacki, Walter; Sam Defranks  
**Subject:** Watertown

Dear Mr. Nemani

I just wanted to follow up on the Revised Certification, Notification and Cleanup Plan Document which I transmitted to you on 22 Dec 2014.

Should you have any questions please contact me via my cell phone below or email me as I will be travelling and not available through the office until 19 Jan 2015.

Best wishes for a great New Year, 2015!

Dave McNichol  
Senior Consultant



500 Bic Drive, Ste. 103, Milford, CT 06461  
T: 203.876.1453 | F: 203.876.1486 | C: 203.856.8388

dmcnichol@trcsolutions.com









UNITED STATES ENVIRONMENTAL PROTECTION AGENCY  
REGION 5  
77 WEST JACKSON BOULEVARD  
CHICAGO, IL 60604-3590

February 2, 2015

REPLY TO THE ATTENTION OF:

LU-9J

Mr. Walter Galacki  
SPX Corporation  
13320 Ballantyne Corporate Place  
Charlotte, North Carolina 28277-2706

Re: SPX Lindberg Facility  
304 Hart Street, Watertown, WI 53094  
Revised Self-Implementing PCB Clean-up Plan

Dear Mr. Galacki:

The U.S. Environmental Protection Agency has completed its review of the proposed Self-Implementation On-Site Clean up and Disposal of PCB Remediation Waste (Plan) report dated December 19, 2014 for the subject site in Wisconsin.

The report submitted by your Consultant, TRC of Milford, Connecticut seeks approval of the cleanup plan in accordance with the Environmental regulation 40 CFR 761.61 (a) (3). The project involves the complete demolition of the facility including the concrete flooring and disposal of the material based on its characterization in accordance with EPA regulations.

**Background:** In advance of a planned self-implementing cleanup, SPX had previously submitted a proposed plan to remediate PCB impacted areas only in accordance with 40 CFR 761.61 (c), based on characterization performed by Delta Consultants for SPX. This plan was approved by EPA by letter of March 28, 2011. Since then, SPX has reassessed the condition of the facility and decided that in its deteriorated state it is best to completely demolish the building and remediate the site. *August 2010*

The Plan calls for demolishing the building and removal of all the concrete flooring and manage it as PCB remediation waste in accordance with 40 CFR 761.61(a) (3), including possible reuse and disposal of the waste. This is to be based on verification sampling (including sub slab sampling) following the remediation. Once remediated, SPX proposes to record a Deed notice for use of the site as for commercial or industrial purposes only, consistent with EPA and WDNR regulations.







**Decision:** Based on the review of the Plan, **approval** to implement the plan is granted subject to the following conditions:

- 1) Within 60 days of the completion of the plan implementation, SPX must submit a Completion Report that includes results of the Verification sampling and details of the operation such as waste quantities and disposal sites.
- 2) Within 60 days of the completion, SPX will record, in accordance with the state law a Deed restriction pertaining to the future land use of the property consistent with the verification results and EPA/WDNR requirements. A draft of the Deed Notice shall be submitted to EPA for review prior to its official filing with the appropriate governmental body. A written certification indicating that the Deed restriction has been filed will need to be submitted to the EPA Regional Administrator.
- 3) At least 45 days before conveying in any manner, ownership or responsibility of the facility or underlying property SPX will notify EPA Region 5 of its intent to convey such ownership or responsibility. The notice will include the date of the intended conveyance, and the contact information of the new owner.

Please note that this acknowledgment does not relieve you from your duty to comply with all other applicable federal, state, and local requirements. If you have any questions, please contact me by e-mail at [nemani.nate@epa.gov](mailto:nemani.nate@epa.gov) or by telephone at (312) 886-3224.

Sincerely,



Nate Nemani, P.E.  
Corrective Action Project Manager  
Remediation and Reuse Branch  
Land and Chemicals Division.

cc: Michael R Schmoller, WDNR  
David McNichol, TRC Consultants.







## Task Details

Request Status : Assignment Determination Task Due Date : 08/10/2015

Submitted Evaluation Assignment Processing Closed

## Request Details

Tracking Number : EPA-R5-2015-008913

Submitted Date : 07/10/2015

Requester : Mr. Carey S. Rosemarin

Perfected Date : 07/13/2015

Organization : Law Offices of Carey S.  
Rosemarin, P.C.

Last Assigned Date : 07/13/2015

Requester Has Account : Yes

Fee Limit : \$25.00

Email Address : csr@rosemarinlaw.com

Request Track : Simple

Phone Number : 847-897-8000

Due Date : 08/10/2015

Fax Number : 312-896-5786

Assigned To : Jessica Wheatley (Region 5)

Address : 500 Skokie Blvd.  
Suite 510

Last Assigned By : Joseph Winfrey (Region 5)

City : Northbrook

State/Province : IL

Zip Code/Postal Code : 60062

## Task Details

LCD and SFD

Task Type : Request Detail

Assigned To : La Nita Marrable (Land and  
Chemicals Division)

Due Date : 08/10/2015

Last Assigned Date : 07/14/2015

Task Submitted Date : 07/13/2015

Last Assigned By : Terri Wilson (Land and  
Chemicals Division)Description : All records relating to the site located at 304 Hart Street in Watertown, Wisconsin 53094  
(the "Site").

Comments :

Submission Details

Case File

Admin Cost

Assigned Tasks

Comments (1)

Review

## Request Handling

Requester Info Available to Yes  
the Public :

Request Perfected : Yes

Request Track : Simple

Perfected Date : 07/13/2015

Fee Category : Commercial

Acknowledgement Sent Date:

Unusual Circumstances ? No

Fee Waiver Requested: No

Fee Waiver Status: N/A

Expedited Processing No  
Requested :

Expedited Processing Status : N/A

## Request Description

WET 560 011 942

Short Description : All records relating to the site located at 304 Hart Street in Watertown, Wisconsin 53094  
(the "Site").

Please produce all records relating to the site located at 304 Hart Street in Watertown, Wisconsin 53094 (the "Site"). The records requested include, but are not limited to, all environmental investigations, complaints and demolition activities relating to the Site. It is believed that the Site is currently owned and/or operated by SPX Corporation, and was formerly owned and/or operated by Lindberg/Blue M Electric Company. My request is limited to the period from January 1, 2013 through the present. If you have any questions concerning this request, or if I can assist in facilitating a response by narrowing the request, or otherwise, please call me at 847-897-8000 x11. Thank you for your assistance.  
Carey S. Rosemarin

No record per Susan Friedman









Writers Direct Dial: 704-808-3751  
Writers Direct Fax: 704-752-4578  
E-Mail Address: [walter.galacki@spx.com](mailto:walter.galacki@spx.com)

October 22, 2014

USEPA  
Region 5  
TSCA/PCB Section  
77 West Jackson Boulevard  
Chicago, IL 60604-3590  
Attn: N. Nemani, L-8J

Re: SPX Lindberg Facility  
304 Hart Street  
Watertown, WI 53094

Gentlemen;

As recently discussed between TRC, SPX's environmental consultant, and USEPA's Nathan Nemani, SPX Corporation has had a change in plans and now intends to completely demolish and remediate the named facility. SPX received EPA approval (March 28, 2011) for a partial removal of PCB contaminated flooring along with cleaning and encapsulating other PCB impacted floor areas. Based on the deteriorating condition of the building and a request from the City for building evaluation, SPX is requesting EPA's modified/amended approval for a complete removal of all flooring with PCB contaminant concentrations greater than 10 mg/kg. SPX believes that a complete removal of the PCB impacted areas above 10 mg/kg and complete demolition of the facility represents a permanent remedy for the facility and is therefore a better and more complete remedial approach.

SPX proposes to remove all of the PCB contaminated flooring proposed in the previous approval and a small additional portion. As discussed, SPX is relying upon the work performed by Delta Consultants, "PCB Assessment Report" dated August 11, 2010; in particular Figures 6 and 7 from that and related reports which were previously submitted to EPA and are attached for reference. Rather than estimate a 10 mg/kg line (as the shaded areas on the Figures have done), SPX is

SPX CORPORATION  
13320 BALLANTYNE CORPORATE PLACE  
CHARLOTTE, NC 28277-2706  
UNITED STATES OF AMERICA

[www.spx.com](http://www.spx.com)







N. Nemani  
October 22, 2014  
Page 2

proposing to have its' contractor remove the flooring to the next measured core where there has been a below 10 mg/kg measurement. Since there has been no use of the building in the intervening time, the bright white core patches are easy to locate. Please see the marked Figures 6 and 7 attached. SPX believes this increased floor removal will provide more certainty that removal has occurred to less than 10 mg/kg. Also, such an approach will reduce the need for confirmation sampling after concrete removal.

SPX believes this is the most prudent and practical approach because most of the remainder of the shaded floor areas are bounded by walls providing a practical limit for removal. The small area outside the rail/truck loading pad (see No. 2) will be subject to a removal until confirmed by post-excavation samples.

At this time SPX is considering removal and disposal of the impacted concrete at either the Heritage or U S Ecology facilities. No shipment would occur until and unless EPA has been notified and approval secured.

Since SPX has recently funded this work, received local approval from the City, and hired a contractor, your earliest response would be most appreciated. Short term work while we await your response will include asbestos related removal and demolition related preparation activities. SPX wishes to thank you for your consideration and review. Please call me directly or Dave McNichol of TRC (office: 203-876-1453, cell: **nonrespons**) if you have any questions.

Very truly yours,



Walter Galacki  
Director, Environmental

cc: D. McNichol -TRC  
S. DeFranks – Apollo


Enclosure







② New Remedial Unit













Fig 7







MATCH LINE



**FIGURE 7**  
**PROPOSED REMEDIATION METHODS**  
**SPX LINDBERG FACILITY**  
**304 HART STREET**  
**WATERTOWN, WISCONSIN**

PROJECT NO.	WAT-000000	
SUBMITTAL NO.	1	
DATE	11/25/00	
REVISIONS		
NO.	DATE	DESCRIPTION
1	11/25/00	ISSUED FOR PERMIT



- LEGEND**
- UNUSUED DOORWAY
  - CURRENT DOORWAY
  - COMPLETE CONCRETE REMOVAL
  - WASH/PAUSE AND EPOXY ENCASUREMENT
  - DOUBLE WASH/PAUSE (SUBPART 2) AND EPOXY ENCASUREMENT
  - DOUBLE WASH/PAUSE (SUBPART 2) NO EPOXY

D -> New Perimeter Limit









## Revisions to Risk-Based Remediation Plan, Section 3

**Karen Thole** to: Nate Nemani

Cc: Virginia.Sunde, dan.mcgrade

12/06/2010 02:18 PM

3 attachments



PCB Remediation Plan REVISED SECTION 3.pdf



Fig7\_Proposed Remediation Methods.pdf

Nate,

Thank you for meeting with us during the November 29, 2010 telephone conference to discuss the Risk-Based Remediation Plan for the SPX Lindberg facility in Watertown, Wisconsin. I have attached Section 3 of the report, which has been revised to reflect the results of our meeting. I have also attached revised Figures 4 and 7.

Please let me know if you have any additional questions or comments. We look forward to receiving your approval of the plan in January 2011.

*Karen J. Thole, P.G.  
Project Hydrogeologist*

Delta Consultants  
5910 Rice Creek Parkway, Suite 100  
Shoreview, MN 55126

(651) 697-5203 - direct dial  
(800) 477-7411 - toll free  
(651) 639-9473 - fax

[kthole@deltaenv.com](mailto:kthole@deltaenv.com)

**CONFIDENTIALITY NOTICE:** This e-mail and the document(s) accompanying this e-mail contain confidential information which is legally privileged. The information is intended only for the use of the intended recipient named above. If you are not the intended recipient, you are hereby notified that any disclosure, copying, distribution, or the taking of any action in reliance on the contents of this e-mail and its attachments, except its direct delivery to the intended recipient named above, is strictly prohibited. If you have received this e-mail in error, please notify us immediately by telephone.







### **3.0 CLEANUP PLAN**

The SPX Lindberg facility is a manufacturing and office building. PCB-contaminated concrete is present throughout the manufacturing portion of the facility. Should a self-implementing cleanup be conducted, a cleanup level for bulk PCB remediation waste of  $\leq 1$  mg/kg would be required without further conditions per 40 CFR 761.61(a)(4)(i)(A). However, an alternative, risk-based cleanup level may be used, pending EPA approval, in accordance with 40 CFR 761.61(c). Based on preliminary conversations with personnel from EPA Region 5 and the Wisconsin Department of Natural Resources (WDNR), a risk-based cleanup level of  $\leq 10$  mg/kg PCBs may be an acceptable site-specific cleanup level for this facility.

A quantitative human health or environmental risk assessment has not been conducted. With the exception of the concrete pad in the rail spur loading area, the PCB contamination is located within the confines of the facility building. (Vertical bulk concrete sampling results demonstrate that the PCBs have not penetrated the concrete floor to the underlying soil.) Since the contaminated areas which will remain at the property following the proposed cleanup are confined within the physical enclosure of the building, no associated risks to the environment are anticipated. Access to the contaminated areas is provided by entrance doors which are currently locked. Under potential future use conditions, the anticipated use of the building is industrial. The potential occupational exposure in this scenario stems primarily from dermal contact with the contaminated floor.


The proposed site cleanup presented below includes off-site disposal, engineered controls, and a deed restriction to limit exposure. Based on its industrial use and limited accessibility, a risk-based cleanup level of  $\leq 10$  mg/kg is being requested for this facility. Approximately 20,650 square feet of concrete contains PCBs at concentrations greater than 10 mg/kg (**Figure 6**).


The following remediation methods are proposed for the facility in order to address the PCBs at concentrations greater than 10 mg/kg:

- Bulk PCB Remediation Waste removal and off-site disposal of the 700 square-foot concrete pad in the rail spur loading area.
- Continued Use Authorization, which includes cleaning per Subpart S and two coats of epoxy, for the in-place management of 12,150 square feet of PCB-contaminated, bare concrete flooring.

what about human (future workers?)  
○  
> 10 mg / 100 cm<sup>2</sup>



≤ 10 mg / 100 cm<sup>2</sup>  Continued Use Authorization, which includes superficial cleaning and two coats of epoxy, for the in-place management of 7,000 square feet of PCB-contaminated, epoxy-coated concrete flooring.

✓ • Bulk PCB Remediation Waste removal and off-site disposal of approximately 800 square-feet of PCB-contaminated concrete flooring located at (8) non-contiguous locations. 

The locations within the facility proposed to be cleaned by these remediation methods are shown in **Figure 7.**

### **3.1 Bulk PCB Remediation Waste Removal and Disposal**

J A 16-foot by 43-foot concrete pad located in the in the rail spur loading area to the north the facility building was found to contain PCBs at concentrations greater than 10 mg/kg (**Figure 7; Appendix A, Photograph 1**). A bulk concrete sample collected from Concrete 36 contained 201 mg/kg PCBs in the 0 to 1 inch sample interval. In order to manage the PCBs in this area, SPX will remove the entire concrete pad in accordance with 40 CFR 761.61(a)(5)(i). The bulk PCB remediation wastes will be managed and disposed off-site in a TSCA-permitted landfill according to the applicable waste classification and disposal regulations as specified under 40 CFR 761.61(a)(5)(i)(B)(2).

Following removal of the concrete pad, a confirmation sample will be collected from the soil beneath the location of Concrete 36. This sample will be analyzed for PCBs by EPA Method 8082. A bulk concrete sample previously collected from Concrete 36 contained 2.29 mg/kg PCBs in the 1 to 3 inch sample interval. Bulk concrete samples collected from the other five locations in the concrete pad did not detect the presence of PCBs at a depth of 1 to 3 inches, so no additional confirmation sampling will be performed beneath the concrete pad. Should the soil sample contain PCBs at a concentration of ≤1 mg/kg, the cleanup will be considered complete. If the soil sample contains >1 mg/kg PCBs, additional soil sampling would be conducted and soils containing >1 mg/kg PCBs would be removed and disposed off-site along with the concrete pad.

### **3.2 Continued Use Authorization**

✓ The 40 CFR 761.30(p) *continued use of porous surfaces contaminated with PCBs regulated for disposal by spills of liquid PCBs* authorization will be implemented for the in-place management of 19,150 square feet of PCB-contaminated concrete located within the



facility. The proposed cleanup level for the work described in this section is  $\leq 10$  mg/kg PCBs.

The proposed cleanup area has been subdivided into two distinct areas with respect to the surface condition of the concrete. The first area consists of 12,150 square feet of bare concrete flooring stretching from the north end of the facility to approximately 440 feet to the south, including the loading dock located on the west side of the building (**Figure 7; Appendix A, Photographs 2 through 5 and 8**). The second area consists of a 7,000-square foot former assembly area near the southern end of the facility (**Figure 7; Appendix A, Photographs 6 and 7**). The floor in this area is covered with a white epoxy coating.

### **3.2.1 PCB Source Control**

The first step of implementing the 761.30(p) continued use authorization requires the removal of the source causing the release of PCBs. No PCB releases have been reported or are known to have occurred within the facility. The results of the investigation discussed above do not indicate a point source of the PCB contamination. The results of a Phase I Environmental Site Assessment (EA) performed at the facility indicated the potential historical presence of PCBs related to the former manufacture of electrical transformers at the facility. According to information presented in the EA report, dated September 23, 2009:

*The second suspect REC consists of the former manufacture of electric transformers at the Subject Property by the Hevi-Duty Company in the 1950's. Historically, manufacturers of transformers were known to employ dielectric fluids containing polychlorinated biphenyls (PCBs). This condition is characterized as a suspect REC since no direct evidence in the form of spills or releases of transformer fluids are known, nor have any indications of the use of PCB-containing fluids been directly identified at the Subject Property. However, the manufacturing of electric transformers at the Subject Property is indicated in a 1956 Sanborn map and the Hevi-Duty Company is known to have historically used PCB containing transformer fluids at other facility locations in the United States.*

Information regarding Hevi-Duty Company historical operations was obtained from the SolaHD website (<http://www.solaheviduty.com>). According to the company's historical summary, the combined operations of transformer and furnace manufacturing were moved to Watertown, Wisconsin in 1953. In 1962, a limited portion of the Watertown facility produced the larger transformers with a maximum rating of 2000 KVA. All transformer production at the facility ended in 1971.



### **3.2.2 Decontamination and Coating Methods**

Prior to the initiation of cleanup activities at the facility, all moveable equipment and materials will be removed from the areas to be cleaned. The 12,150 square feet of bare, PCB-contaminated concrete floor will be cleaned in accordance with the double wash/rinse procedure described in 40 CFR 761 Subpart S. This procedure is intended for the decontamination of non-porous surfaces, but 761.30(p) requires that this method be used to prepare PCB-contaminated concrete for encapsulation. Following an initial vacuum to remove loose dust and bird waste, the surface washing steps in this area will include 1) high-pressure steam wash with concrete cleaner/degreaser, 2) potable water rinse, 3) power scrub with a cleaning/degreasing and muriatic acid etchant solution, and 4) high-pressure steam rinse.

The 7,000 square feet of epoxy-coated, PCB-contaminated concrete floors will be cleaned in a manner less stringent than the double wash/rinse procedure. The reason for this is that while bulk concrete samples collected from below the epoxy-coated surface in this area contained elevated levels of PCBs, wipe samples taken from the top of the epoxy-coated surface did not exhibit PCBs above 10 µg/100 cm<sup>2</sup>. Following an initial vacuum to remove loose dust and bird waste, the surface washing steps in this area will include a 1) high-pressure steam wash with concrete cleaner/degreaser, 2) a light scuffing of the epoxy-coated surface with 100+ grit sandpaper, and 3) a final vacuum and rinse.

Following the surface washing activities and once the surface has been allowed to dry for a minimum of 24 hours, an epoxy encapsulant will be placed on the concrete surface according to the requirements of 40 CFR 761.30(p)(1)(iii)(A). Two coats of epoxy will be applied to the floor surface. (The two coats of epoxy will consist of contrasting colors so that any wearing of the topcoat can be detected. In the area where a white epoxy coating already exists, one additional coat will be applied in a contrasting color.)

Once the epoxy has dried, labels will be placed on the encapsulated floor surfaces to indicate that PCBs remain in the underlying concrete as specified under 40 CFR 761.30(p)(1)(iii)(B). The labels, described in 761.45, will be applied at the entrances, corners, and central portions of the encapsulated area.



### **3.2.3 Disposal**

Wastes generated during the double wash/rinse procedure and encapsulation may include water mixed with detergent, water mixed with spent degreaser, used absorbent materials, and other equipment. These wastes will be managed according to applicable waste classification and disposal regulations as specified under 40 CFR 761.378(c).

### **3.3 Bulk PCB Remediation Waste Removal and Disposal**

Besides the 19,150 square feet of PCB-contaminated concrete described above, there were eight non-contiguous concrete sample locations exhibiting PCB concentrations greater than 10 mg/kg (**Figure 7**). These locations include the following:


- Concrete 53 - 12.67 mg/kg PCBs at 0-1 inch, 1.06 mg/kg PCBs at 1-3 inches (Wipe B5 had 2.0 µg/100 cm<sup>2</sup> PCBs);
- Concrete 103 - 40.0 mg/kg PCBs at 0-1 inch, non-detect at 1-3 inches;
- Concrete 178 - 11.00 mg/kg PCBs at 0-1 inch, (Wipe A7 had 4.6 µg/100 cm<sup>2</sup> PCBs);
- Concrete 230 - 11.50 mg/kg PCBs at 0-1 inch, non-detect at 2-4 inches (Wipe C3 had 5.6 µg/100 cm<sup>2</sup> PCBs);
- Concrete 239 - 22.0 mg/kg PCBs at 0-1 inch, (Wipe C6 was non-detect);
- Concrete 252 - 11.0 mg/kg PCBs at 0-1 inch, non-detect at 2-4 inches;
- Concrete 272 - 10.3 mg/kg PCBs at 0-1 inch, non-detect at 2-4 inches (Wipe C4 had 4.5 µg/100 cm<sup>2</sup>); and
- Concrete 370 - 16.0 mg/kg PCBs at 0-1 inch.

Given the limited areal and vertical extent of PCBs in these eight locations, SPX will cut out and remove the 10-foot by 10-foot (100-square foot) section of concrete floor surrounding each sample location (**Figure 7**). The entire thickness of the concrete floor will be removed. The bulk PCB remediation wastes will be managed and disposed off-site in a TSCA-permitted landfill according to the applicable waste classification and disposal regulations as specified under 40 CFR 761.61(a)(5)(i)(B)(2). Since the entire thickness of the concrete floor will be removed in these areas, no confirmation sampling will be conducted.









LEGEND:

⊠ - UNUSED DOORWAY

◻ - CURRENT DOORWAY

• - CONCRETE SAMPLE LOCATION

10.89 - PCB SAMPLE RESULTS IN MILLIGRAMS PER KILOGRAM (mg/kg)


ND - NOT DETECTED

LAB AND OFFICE



**FIGURE 4**  
**PCB RESULTS - 0-1 INCH**  
**SPX LINDBERG FACILITY**  
**304 HART STREET**  
**WATERTOWN, WISCONSIN**


PROJECT NO. BM0809245	PREPARED BY KT	DRAWN BY DD
DATE 7/12/10	REVIEWED BY	FILE NAME Watertown-B

















## **SUMMARY OF RISK-BASED REMEDIATION PLAN FOR PCB-CONTAMINATED CONCRETE**

**SPX Lindberg Facility  
304 Hart Street  
Watertown, Wisconsin**

### **Background Info**

- SPX Lindberg facility consists of a 174,000 square foot manufacturing and office building on approximately 5.3 acres.
- The facility manufactured electrical transformers in the 1950s through 1971.
- From 1971 to 2005, the facility manufactured industrial ovens, refrigeration units, environmental test chambers, industrial manufacturing furnaces, and custom products.
- Manufacturing operations were terminated in late 2005.

### **Site Characterization Data**

- A total of 72 wipe samples were collected from the floor throughout the facility in an approximate 60-foot grid pattern. Ten wipe samples indicated PCB concentrations greater than 10  $\mu\text{g}/100\text{ cm}^2$ , with the highest being 59.7  $\mu\text{g}/100\text{ cm}^2$ .
- A total of 585 bulk concrete samples were collected from 406 locations throughout the facility. Of the 406 near-surface (0 to 1 inch deep) concrete samples collected, 95 samples exhibited PCB concentrations above 10 mg/kg PCBs. These sample locations are shown as the shaded areas in **Figure 6**.

### **Proposed Remediation Plan**

- Based on its industrial use and limited accessibility, a risk-based cleanup level of  $\leq 10$  mg/kg is being requested for this facility.
- Approximately 20,650 square feet of concrete contains PCBs at concentrations greater than 10 mg/kg (**Figure 6**).
- Based on results of sample analysis and condition/location of concrete floor, we have designated 5 separate areas within the facility.
  1. 700 square-foot concrete pad located outside of building in the rail spur loading area exhibiting PCB concentrations greater than 1 mg/kg (cross-hatch pattern on **Figure 7**).
  2. 12,150 square feet of bare concrete flooring exhibiting PCB concentrations greater than 10 mg/kg (shaded on **Figure 7**).
  3. 7,000 square feet of epoxy-coated concrete flooring exhibiting PCB concentrations greater than 10 mg/kg (diagonal-hatch pattern on **Figure 7**).
  4. Eight non-contiguous sample locations exhibiting PCB concentrations greater than 10 mg/kg (horizontal-hatch pattern on **Figure 7**).
  5. The remaining concrete flooring exhibiting PCB concentrations less than or equal to 10 mg/kg PCBs (not shaded on **Figure 7**).



- Proposed remediation plan for each of the 5 areas is as follows:

**1. Concrete Pad in Rail Spur Loading Area**

- Remove the entire concrete pad in accordance with 40 CFR 761.61(a)(5)(i).
- Manage and dispose the bulk PCB remediation wastes off-site according to the applicable waste classification and disposal regulations as specified under 40 CFR 761.61(a)(5)(i)(B)(2).
- Collect confirmation sample from the soil beneath the location of sample Concrete 36 (210 mg/kg PCBs) for laboratory analysis for PCBs by EPA Method 8082.

**2. Bare Concrete Flooring with PCBs >10 mg/kg**

- Continue to use contaminated concrete floor in accordance with the Continued Use Authorization as specified in 40 CFR 761.30(p)
- Clean accessible floors per the double wash rinse procedure in Subpart S.
- Apply two coats of solvent resistant and water repellent epoxy of contrasting colors.
- Mark the encapsulated floor surfaces with labels to indicate that PCBs remain in the underlying concrete as specified under 40 CFR 761.30(p)(1)(iii)(B).
- Record a notation on the deed to the property within 60 days of the completion of the cleanup activities in accordance with 40 CFR 761.61(a)(8)(i).

**3. Epoxy-Coated Concrete Flooring with PCBs >10 mg/kg**

- Continue to use contaminated concrete floor in accordance with the Continued Use Authorization as specified in 40 CFR 761.30(p)
- Clean accessible floors in a manner less stringent cleaning method than the double wash rinse procedure to maintain the integrity of the existing epoxy surface.
- Apply two coats of solvent resistant and water repellent epoxy of contrasting colors.
- Mark the encapsulated floor surfaces with labels to indicate that PCBs remain in the underlying concrete as specified under 40 CFR 761.30(p)(1)(iii)(B).
- Record a notation on the deed to the property within 60 days of the completion of the cleanup activities in accordance with 40 CFR 761.61(a)(8)(i).


**4. Concrete Flooring at Non-Contiguous Locations with PCBs >10 mg/kg**

- Continue to use contaminated concrete floor in accordance with the Continued Use Authorization as specified in 40 CFR 761.30(p)
- Clean accessible floors per the double wash rinse procedure in Subpart S.
- Collect bulk concrete confirmation sample at each location for laboratory analysis for PCBs by EPA Method 8082.
- If the sample result indicates a PCB concentration of  $\leq 10$  mg/kg, the sample location would be considered to be a part of Area 5 and remediated accordingly.
- If the sample result indicates a PCB concentration greater than 10 mg/kg, the sample location would be considered to be a part of Area 2 and remediated accordingly.


**5. Remaining Concrete Flooring**

- Continue to use concrete floor with no remediation.
- Record a notation on the deed to the property within 60 days of the completion of the cleanup activities in accordance with 40 CFR 761.61(a)(8)(i) restricting the property to industrial use only.











August 11, 2010

Ms. Susan Hedman  
Regional Administrator  
US EPA Region 5  
77 West Jackson Boulevard  
Chicago, IL 60604

Mr. Matthew Frank  
Secretary  
Wisconsin Department of Natural Resources  
P.O. Box 7921  
Madison, WI 53707-7921

Mr. Jeff Ackerman  
Wisconsin DNR South Central Region  
Division of Air and Waste  
Remediation and Redevelopment  
3911 Fish Hatchery Road  
Fitchburg WI 53711

Subject: *Risk-Based Remediation Plan for PCB-Contaminated Concrete*  
SPX Lindberg Facility  
304 Hart Street  
Watertown, Wisconsin  
Delta Project No. 9M0909245

RECEIVED  
DIVISION FRONT OFFICE

AUG 17 2010

LAND AND CHEMICALS DIVISION  
U.S. EPA - REGION 5

RECEIVED  
DIVISION FRONT OFFICE

AUG 17 2010

LAND AND CHEMICALS DIVISION  
U.S. EPA - REGION 5

RECEIVED

AUG 16 2010

U.S. E  
OFFICE OF REGIONAL ADMINISTRATION

AUG 17 2010



Dear Ms. Hedman, Mr. Frank, and Mr. Ackerman:

The purpose of this correspondence is to submit the *Risk-based Remediation Plan for PCB-Contaminated Concrete* for management of polychlorinated biphenyl (PCB)-contaminated concrete at the SPX Lindberg facility, a manufacturing facility located in Watertown, Wisconsin. This report fulfills the application requirements of the Environmental Protection Agency (EPA) Toxic Substance Control Act (TSCA) PCB regulations, 40 CFR 761.61(c) *Risk-based disposal approval* for PCB remediation waste.

SPX is proposing to implement the 40 CFR 761.30(p) *continued use of porous surfaces contaminated with PCBs regulated for disposal by spills of liquid PCBs* authorization for the in-place management of PCB-contaminated concrete at the facility and is requesting a risk-based cleanup level of  $\leq 10$  milligrams per kilogram (mg/kg) PCBs.

If you have any questions regarding the attached report, please contact me at (651) 697-5203.

Sincerely,

**DELTA CONSULTANTS**

Karen J. Thole, P.G.  
Project Hydrogeologist

Enclosure

cc. Dan McGrade - SPX Corporation  
Virginia Sunde - SPX Corporation

a member of:











Writers Direct Dial: 704-808-3751  
Writers Direct Fax: 704-752-4578  
E-Mail Address: [walter.galacki@spx.com](mailto:walter.galacki@spx.com)

November 19, 2014

USEPA  
Region 5  
TSCA/PCB Coordinator  
77 West Jackson Boulevard  
Chicago, IL 60604-3590  
Attn: N. Nemani, L-8J

Re: SPX Corporation former Lindberg Facility  
304 Hart Street  
Watertown, WI 53094

Gentlemen:

As recently discussed between TRC, SPX's environmental consultant, and USEPA's Nathan Nemani, SPX is submitting this information to notify and certify to the Agency and all concerned (the EPA Regional Administrator, the Secretary of the WI DNR, Jefferson County, and the City of Watertown) that SPX intends to conduct a "self-implementing on-site cleanup and disposal of PCB remediation waste" for the captioned site.

SPX had previously received EPA's approval for a partial removal of PCB surficially contaminated concrete flooring and encapsulation of other flooring (40 CFR 761.61 (c)) dated 28 March 2011. As discussed, based on the deteriorating condition of the building and in consultation with the City, SPX has decided to demolish the building and all associated structures and completely remediate the facility in accord with 40 CFR 761.61 (a).

Enclosed is documentation covering the nature of the PCB contamination, the summary of procedures and methods for sampling, characterization and analysis, the location and extent of the contamination, and a cleanup plan including schedule, disposal plan and the demolition and remedial approach.

SPX CORPORATION  
13320 BALLANTYNE CORPORATE PLACE  
CHARLOTTE, NC 28277-2708  
UNITED STATES OF AMERICA

[www.spx.com](http://www.spx.com)








Nathan Nemani, USEPA  
November 19, 2014  
Page 2

Since we believed that we were close to an EPA approval several weeks ago, we are asking for an expedited review of this material in order that our demolition and remediation contractor may continue with his work at the site. Should you need any further information please contact our consultant, Dave McNichol of TRC immediately.

Thank you in advance for your attention to this matter.

Very truly yours,



Walter Galacki  
Director Environmental  
For SPX Corporation, Owner and Operator and Successor in Interest of the  
former SPX Lindberg site

W/enclosures

CC: Jefferson County Health Department, Environmental Health Section  
WI DNR, Remediation and Redevelopment Program  
City of Watertown, J.J. Holloway, PE  
TRC, Dave McNichol  
Nixon Peabody, Al Floro







## TABLE OF CONTENTS

### 1.0 Introduction

#### 1.1 Purpose

#### 1.2 Background

### 2.0 Nature of PCB Contamination

### 3.0 Cleanup Plan

#### 3.1 Bulk PCB Remediation Waste Removal and Disposal

#### 3.2 Schedule

#### 3.3 Verification

#### 3.4 Site Restoration

### 4.0 Recordkeeping

Figure 1. PCB Concrete Removal (after Delta Fig. 6)

## Appendices

- A. Apollo Dismantling Inc.-Waste Management Plan
- B. Delta Consultants Report "Risk-Based Remediation Plan for PCB Contaminated Concrete" ,  
December 6, 2010. Report Extract.







## 1.0 INTRODUCTION

### 1.1 PURPOSE

SPX Corporation (SPX) wishes to perform a *Self-implementing on-site cleanup and disposal of PCB remediation waste* at the SPX Lindberg facility located at 304 Hart Street, Watertown, WI 53094. The entire project also involves the complete demolition and remediation of the facility. SPX had received EPA's approval for a risk-based approach under 40 CFR 761.61(c). See EPA letter dated March 28, 2011.

SPX, however, no longer believes the facility is useful in its' deteriorated condition and now wishes to completely demolish the buildings and remediate the site and seeks, with the help of the City of Watertown, to find a redeveloper. Thus, SPX is seeking EPA's approval under 40 CFR 761.61(a) in order to perform a *Self-implementing on-site cleanup and disposal of PCB remediation waste*.

### 1.2 BACKGROUND

Delta Consultants, Shoreview, MN has investigated the Lindberg facility for PCBs and has reported on those investigations. EPA's prior approval was based upon that reporting. TRC has been engaged by SPX to manage/oversee the remediation and demolition. As such TRC and SPX are continuing to rely upon Delta's earlier work and their report "Risk-Based Remediation Plan for PCB-Contaminated Concrete" dated August 2, 2010 and (the subsequent modifications and revisions) it is incorporated herein. For the reader's convenience and reference the material follows this report.

The PCB contamination observed at the former Lindberg facility is believed to have been from the manufacture of electrical transformers during a period from 1953 until 1971. No spill event nor history has been identified through a historical review as well as interviews with former employees. The primary PCB contamination is of concrete flooring (within the building) and to a lesser extent a small area outside the building which is a small loading/shipping pad and adjacent soils. Notably, the PCB contamination is not at depth in the concrete flooring, thus PCB contamination is not expected in the substrate beneath any flooring. See especially the Figures in the Delta Report.

SPX, in conjunction with the facilities full demolition and remediation, will remove all Asbestos Containing Building Materials (ACM), Universal Waste (batteries, lamps-both florescent and metal-halide, mercury in electrical components, CPUs, etc.), decommission all firewater, electrical, water and sewer, remove all oils, lubes, etc. For the demolition all C & D waste will be disposed at the local Subtitle D landfill operated by Waste Management and located in Watertown. The ACM is to be transported and disposed at the Pheasant Run Landfill operated by Waste Management and located in Bristol, WI. Universal waste is destined for Mercury Waste Solutions in Union Grove, WI. And, the PCB concrete along with a minor amount of soil (loading pad area) would be manifested and transported to a Subtitle C Landfill operated by Heritage Environmental Services located in Roachdale, IN.







## 2.0 NATURE OF PCB CONTAMINATION

The nature of the contamination is fully described and explained by Delta in their report. The sampling, the analysis, the PCB results and the graphic (figures) pattern of PCB contamination is all contained in section 2 of their report. SPX and TRC are relying on this information for the Cleanup discussion which follows in section 3. Please see section 2 of the Delta report for a description of the nature of the contamination.







### 3.0 CLEAN UP PLAN

The SPX former Lindberg facility had been principally a manufacturer of industrial ovens, furnaces, and environmental test chambers with an associated office activity. Early in its history the facility had also produced electrical transformers. The manufacturing areas were in some cases added buildings and in other cases large rooms or other functional areas within a given building-see figures. SPX will perform a self-implementing clean up resulting in PCB concentrations for the bulk PCB remediation waste of less than 1 mg/kg and unlimited use for the remaining land after all remediation and demolition are completed (40 CFR 761.61(a)(4)(i)(A)). The proposed clean up includes the removal of PCB contaminated concrete, the removal of a minor quantity of PCB contaminated soils and a loading pad (only outdoor area), and the transportation and disposal of these materials to a RCRA Subtitle C facility all as more fully described below.

#### 3.1 Bulk PCB Remediation Waste Removal and Disposal

SPX intends to remove all of the concrete flooring shown on Figure 1. The contractor hired by SPX, Apollo Dismantling, has mobilized to the site and is currently preparing for the demolition and remediation. At the moment Apollo and its subcontractors are removing all ACM, removing all Universal wastes, collecting all lamps and ballasts, and draining and arranging for utility shutoff and blocks. Once this work is completed Apollo had planned to cut out and remove all PCB concrete for Title C Landfill disposal. See schedule below.

SPX proposes to remove all of the PCB contaminated flooring proposed in the previous approval (all of the areas which were to be removed and all the areas which were to be encapsulated). See relevant parts of Delta section 3. The removal will be in all cases to full floor depth. In addition, SPX proposes to go beyond the limits previously estimated as the 10 mg/kg line by Delta; namely to the next core location (still locatable) where a measured result is less than 10 mg/kg. Thus existing measured values and full depth floor removal ensures the objective is met.

Remaining flooring will then be removed from all areas (rooms and/or buildings) where a PCB floor removal has occurred. The material will be sized and placed in a single on site pile for further use on site, if possible. Prior to any on-site use the pile will be sampled and analyzed to ensure that the material is less than 1 mg/kg PCB. If less than 1 mg/kg PCB, it is candidate material for onsite use to fill any basement voids from the demolition. Should the pile material test between 10 and 1 mg/kg it will not be used onsite but will be disposed into a Subtitle D landfill, either for temporary cover or as fill. Thus any PCB concrete greater than 10 mg/kg (and minor soils quantity) will be disposed at a Subtitle C facility; any PCB concrete between 10 and 1 mg/kg will be disposed in a Subtitle D landfill facility; and,







any PCB concrete less than 1 mg/kg may be retained for use to fill basement voids onsite-or if an excessive quantity exists may also be disposed in a Subtitle D landfill facility.

### 3.2 SCHEDULE

The proposed schedule is as follows:

ACM removal 24 Oct-26 Nov

PCB bulk removal 8 Dec-15 Jan

Lights/ballasts/U waste 17 Nov-15 Dec

Demolition 8 Dec-15 Feb

Restoration Spring 2015

### 3.3 Verification

Verification sampling is necessary for two areas. The removal of the concrete pad in the rail car loading/unloading area (including soils) and the concrete removed pile which will be less than 10 mg/kg and likely less than 1 mg/kg. In both cases EPA Method 8082 will be used for sample analysis. The outdoor excavation will be sampled with 2-sidewalls samples and a bottom invert sample. The concrete pile will be sampled with 6 samples, composited to 2 for analysis.

Since there was no indication in any of the Delta investigation (more than 585 concrete cores) of PCB at floor depth, it is not necessary to sample any substrate below the flooring.

### 3.4 Site Restoration

After completion of all the demolition and remediation activities the site will be restored. The front side walk on Hart Street will remain. The voids of former basement areas will be filled with the concrete from the less than 1 mg/kg pile (assuming it has been verified as above described). After the voids are filled fresh stone will be imported to cover the concrete areas. This will be somewhat crowned to allow that no ponding should occur over time. The property will then be idle until redevelopment can be planned and implemented.







#### 4.0 RECORDKEEPING


A file containing all sampling, analysis, results, graphic depictions of results, shipping and manifesting documents including weight tickets and summaries will be created. Several electronic copies of the record compilation will be made. An electronic copy will be forwarded to USEPA Region 5 PCB Coordinator and to WI DNR PCB Section.

Since it is a cleanup to less than 1 mg/kg PCB no further actions are anticipated.















**Waste Management Plan**  
November 2014

**SPX - Lindberg**  
**304 Hart Street**  
**Watertown, WI 53094**

**Prepared for:**



**13320 Ballantyne Corporate Place**  
**Charlotte, NC 28277**

**Prepared by:**

**APOLLO DISMANTLING**  
**4511 Hyde Park Blvd.**  
**2<sup>nd</sup> Floor**  
**Niagara Falls, NY 14305**







# APPOLO DISMANTLING SERVICES

## Waste Management Program

### 1.0 Introduction

The objective of the *Apollo Dismantling Waste Management Plan* is to characterize, manage, containerize, transport and dispose of all regulated, hazardous, non-hazardous, and recyclable waste streams during the remediation and demolition activities associated with the 170,000 sq. ft. SPX industrial complex located at 304 Hard Street, Watertown, Wisconsin 53094.

Apollo will perform all work in accordance with the applicable regulations and standard industry practice. In addition, Apollo will conduct a general assessment of the conditions and materials associated with the facility. It is anticipated that the *Waste Management Plan* will be revised as the project progresses to ensure all waste materials are identified and project activities are consistent with waste characterization reports and the applicable regulatory requirements.

### 1.1 Asbestos Abatement Phase

The asbestos abatement phase includes the removal of all previously identified asbestos materials and any additional identified asbestos containing building components. The friable asbestos is pipe insulation and it is located throughout the facility. The non-friable asbestos abatement includes the removal of transite panels on the exterior walls and flooring materials located in various areas. In addition, any other suspect building components (roofing, flashing, window caulk, etc) will be tested for asbestos in accordance with the applicable regulations. All of the asbestos containing building materials will be identified, quantified, packaged and disposed of in accordance with the applicable federal, state and local regulations.

### 1.2 Debris Removal and C&D Waste

The debris clean-up phase includes the removal of all garbage, paper, cardboard, desks, rugs, partitions, wood and other general debris found within and around the exterior of the facility. This debris and other non-regulated construction and demolition waste generated during the demolition work will be placed in dumpsters or loaded into dump trailers and disposed of in accordance with the applicable regulations.

### 1.3 PCB Concrete-RECRA

A PCB assessment report completed by Delta Engineers was completed in August 2010. This report outlines the areas of contaminate PCB concrete that will be handled as RECRA Waste. The majority of the RECRA waste will be removed prior to mass demolition and staged for loading. The building area (approx. 7,000 SF) which contains a basement below the PCB contaminated concrete 1<sup>st</sup> floor slab will be performed after the above grade building structure has been demolished.







## APPOLO DISMANTLING SERVICES

### 1.4 PCB Concrete – NON-RECRA, Masonry, Concrete Slabs and Foundations

Apollo will demolish, remove, downsize (12" minus), and stockpile on-site Clean Concrete Slabs and Foundations, NON-RECRA PCB Concrete Slabs, and Masonry debris. Apollo and SPX will determine the final location of stockpile/berms.

### 1.5 Universal Waste

An inventory of Universal Waste was provided in the bid documents. In addition, Apollo will inspect the facility to confirm all universal waste items are identified and collected. If necessary, Apollo will request additional sampling and analysis to be performed to characterize each waste stream as it is collected, identified and packaged. Based on the results of this characterization, and analytical results, Apollo will transport and dispose of materials in the appropriate manner as per the applicable federal, state and local regulations.

## 2.0 Disposal Facilities

Waste recycling/disposal facilities were selected based on several factors including waste types, facility acceptance criteria, regulatory compliance history and price.

### Waste Stream and Disposal Facility

- **C&D Waste**  
Waste Management  
Deer Track Park Landfill  
N6756 Waldmann Ln  
Watertown, Wisconsin 53094  
(920)699-3475
- **Universal Wastes**  
Waste Management  
Mercury Waste Solutions  
21211 Durand Ave  
Union Grove Wisconsin 53182  
(262) 878-2599
- **Steel Scrap**  
LOEB-LORMAN  
1111 South Tenth Street  
Watertown Wisconsin 53094  
(920)390-2260







## APPOLO DISMANTLING SERVICES

- ***Asbestos Waste***  
Waste Management  
Pheasant Run Landfill  
19414 60<sup>th</sup> Street  
Bristol, WI 53104  
(262) 857-7956
- ***PCB Concrete – RECRA***  
Heritage Environmental Services  
4370 West County Road 1275 N  
Roachdale, Indiana 46172  
(765) 435-2704

### **3.0 Documentation**

All applicable local, state and federal documentation and record keeping requirements/guidelines will be followed. Apollo will provide the following:

- Waste Characterization Reports
- Waste Manifest and or Shipping Receipt

The above documents will identify the date the waste is removed from the site, transporter/hauler, waste disposal facility and their applicable state and or federal identification numbers.







**RISK-BASED REMEDIATION PLAN FOR**  
**PCB-CONTAMINATED CONCRETE**

**SPX LINDBERG FACILITY**  
**304 HART STREET**  
**WATERTOWN, WISCONSIN**  
**DELTA PROJECT NO. 9M0909245**

**Prepared for:**

**SPX Corporation**  
**13515 Ballantyne Corporate Place**  
**Charlotte, North Carolina 28277**  
**(704) 752-4430**

**Prepared by:**

**Delta Consultants**  
**5910 Rice Creek Parkway, Suite 100**  
**Shoreview, Minnesota 55126**  
**(651) 639-9449**

**December 6, 2010**







## **TABLE OF CONTENTS**

1.0 INTRODUCTION .....	1
1.1 Purpose.....	1
1.2 Background Information.....	1
2.0 NATURE OF CONTAMINATION .....	2
2.1 PCB Wipe Sampling .....	2
2.2 PCB Bulk Concrete Sampling .....	4
3.0 CLEANUP PLAN.....	6
3.1 Bulk PCB Remediation Waste Removal and Disposal.....	7
3.2 Continued Use Authorization .....	8
3.2.1 PCB Source Control .....	8
3.2.2 Decontamination and Coating Methods.....	9
3.2.3 Disposal .....	10
3.3 Bulk PCB Remediation Waste Removal and Disposal.....	10
4.0 RECORDKEEPING .....	11
5.0 REMARKS .....	12

## **List of Tables**

Table 1	PCB Wipe Sample Analytical Results
Table 2	PCB Bulk Concrete Analytical Results

## **List of Figures**

Figure 1	Site Location Map
Figure 2	PCB Wipe Sample Results Map
Figure 3	Concrete Sample Location Map
Figure 4	PCB Results – 0-1 Inch
Figure 5	PCB Results – Deeper Samples
Figure 6	Proposed Areal Extent of Remediation
Figure 7	Proposed Remediation Methods

## **List of Appendices**

Appendix A	Photograph Log
Appendix B	Wipe Sample Analytical Reports
Appendix C	Bulk Concrete Sample Analytical Reports









UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 5

77 WEST JACKSON BOULEVARD

CHICAGO, IL 60604-3590

REPLY TO THE ATTENTION OF:

OCT 19 2010

LU-9J

Ms. Karen J Thole, P.G.  
Delta Consultants  
5910 Rice Creek Parkway, Suite 100  
St. Paul, Minnesota, 55126

RE: Re. SPX Lindberg Facility  
Watertown, Wisconsin  
Risk- Based Remediation Plan for PCB Contaminated Concrete

Dear Ms. Thole:

The U.S. Environmental Protection Agency, Region 5, has reviewed your request for a Risk- Based Remediation Plan (Plan) approval under 40 C.F.R 761.61(c) of the TSCA Regulations. The Plan was outlined in a report dated August 11, 2010 for PCB Contaminated Concrete at the subject facility.

The report describes a Remediation Plan to address PCB impacted concrete at the facility building located in Watertown, Wisconsin and is preceded by characterization of the concrete floors across the facility. As part of characterization plan for the facility, a number of PCB Wipe samples and PCB Bulk Concrete samples, at varying depth were taken at the facility.

The report describes a proposed clean-up plan that includes off-site disposal of PCB remediation waste, engineered controls and a deed restriction. The proposed plan also calls for leaving in place PCB remediation waste that has a concentration above 10 milligrams per kilogram (mg/kg) PCB in some locations.

A review of the remediation measures in the plan shows that while a portion of the concrete pad exceeding 10 mg/kg is proposed to be removed and disposed off-site per applicable TSCA regulations, there are other areas in the building with concentrations exceeding this value that are proposed to be left in place. It is recognized that specific clean-up procedures are proposed to be implemented for these areas. However, the plan does not address certain issues pertaining to the future use of the facility as it relates to "high/ low occupancy" (as described in the TSCA regulations). This is a factor that is directly linked to potential human exposures and their corresponding risks.

Please provide details on the plans to address the above issues as well as a rationale/justification for the remedial procedures proposed for the different areas and how







leaving greater than 10 mg/kg concentrations in concrete will be protective for planned facility use. Alternatively, you may request a meeting in person or by phone so that the issues can be discussed in more detail.

---

If you have any further questions, please feel free to contact me at [nemani.nate@epa.gov](mailto:nemani.nate@epa.gov) or by phone at (312) 886-3224.

Sincerely,



Nate Nemani, P.E.

Correction Action Project Manager  
Land and Chemicals Division

cc: Jeff Ackerman WDNR









*Ginger*  
**RE: Proposed dates for phone conference**

**Karen Thole** to: Nate Nemani

11/24/2010 02:11 PM

Cc: dan.mcgrade, Virginia.Sunde, Peter Ramanauskas, Mario Mangino

Monday, November 29 at 2:00 pm (Chicago time) works for us. Please call **nonresponsi** and enter passcode **nonre** for the conference call.

Thank you.

Karen J. Thole, P.G.  
Project Hydrogeologist

Delta Consultants  
5910 Rice Creek Parkway, Suite 100  
Shoreview, MN 55126

(651) 697-5203 - direct dial  
(800) 477-7411 - toll free  
(651) 639-9473 - fax

[kthole@deltaenv.com](mailto:kthole@deltaenv.com)

**CONFIDENTIALITY NOTICE:** This e-mail and the document(s) accompanying this e-mail contain confidential information which is legally privileged. The information is intended only for the use of the intended recipient named above. If you are not the intended recipient, you are hereby notified that any disclosure, copying, distribution, or the taking of any action in reliance on the contents of this e-mail and its attachments, except its direct delivery to the intended recipient named above, is strictly prohibited. If you have received this e-mail in error, please notify us immediately by telephone.

---

**From:** Nemani.Nate@epamail.epa.gov [mailto:Nemani.Nate@epamail.epa.gov]

**Sent:** Wed 11/24/2010 1:22 PM

**To:** Karen Thole

**Cc:** dan.mcgrade@spx.com; Virginia.Sunde@spx.com; Ramanauskas.Peter@epamail.epa.gov; Mangino.Mario@epamail.epa.gov

**Subject:** Re: Proposed dates for phone conference

Karen:

The only date and time that seems to work for us is 11/29 ( Monday) at 2:00 PM , Chicago time.

Please confirm if it is OK, ASAP.

Thanks

Nate



NATE NEMANI, P.E.  
RCRA CORRECTIVE ACTION PROJECT MANAGER  
LAND AND CHEMICALS DIVISION  
REMEDIATION AND REUSE BRANCH,  
U. S.EPA, REGION 5 ,  
77 W JACKSON Blvd, CHICAGO, ILLINOIS, 60604, Mail Code: LU-9J  
(312) 886-3224 (PHONE)  
(312) 692-2176 (FAX)  
nemani.nate@epa.gov (e-mail address)

From: "Karen Thole" <kthole@deltaenv.com>  
To: Nate Nemani/R5/USEPA/US@EPA  
Cc: <Virginia.Sunde@spx.com>, <dan.mcgrade@spx.com>  
Date: 11/23/2010 03:28 PM  
Subject: Proposed dates for phone conference

Nate,

Here are a few proposed dates for our telephone conference regarding the Risk-Based Remediation Plan for PCB Contaminated Concrete at the SPX Lindberg facility:

November 29, 30  
December 1, 2, 7, 8, 9

Please let me know if any of these dates work for you.

Attending the telephone conference from SPX will be Virginia Sunde, Assistant Director, Environmental, and Dan McGrade, Director, Environmental.

*Karen J. Thole, P.G.*  
*Project Hydrogeologist*

Delta Consultants



5910 Rice Creek Parkway, Suite 100  
Shoreview, MN 55126

(651) 697-5203 - direct dial  
(800) 477-7411 - toll free  
(651) 639-9473 - fax

[kthole@deltaenv.com](mailto:kthole@deltaenv.com)

**CONFIDENTIALITY NOTICE:** *This e-mail and the document(s) accompanying this e-mail contain confidential information which is legally privileged. The information is intended only for the use of the intended recipient named above. If you are not the intended recipient, you are hereby notified that any disclosure, copying, distribution, or the taking of any action in reliance on the contents of this e-mail and its attachments, except its direct delivery to the intended recipient named above, is strictly prohibited. If you have received this e-mail in error, please notify us immediately by telephone.*







## Nemani, Nate

---

**From:** McNichol, David <DMcNichol@trcsolutions.com>  
**Sent:** Wednesday, November 19, 2014 4:14 PM  
**To:** Nemani, Nate  
**Cc:** Galacki, Walter  
**Subject:** SPX Watertown Notification and Certification for self-implementing on-site cleanup.....  
**Attachments:** TRC USEPA Submit SPX Watertown 11-19-14.pdf

Dear Mr. Nemani:

Attached is a submission containing, we believe, everything you may need to review and approve this PCB activity under 40 CFR 761.61 (a).

Please contact me immediately should you have any questions or require any additional information. Copies are also being distributed to appropriate parties at WI DNR, Jefferson County and the City of Watertown.

We look forward to your response.

Best

Dave McNichol  
Senior Consultant



500 Bic Drive, Ste. 103, Milford, CT 06461  
T: 203.876.1453 | F: 203.876.1486 | C: 203.856.8388  
dmcnichol@trcsolutions.com









Writers Direct Dial: 704-808-3751  
Writers Direct Fax: 704-752-4578  
E-Mail Address: [walter.galacki@spx.com](mailto:walter.galacki@spx.com)

November 19, 2014

USEPA  
Region 5  
TSCA/PCB Coordinator  
77 West Jackson Boulevard  
Chicago, IL 60604-3590  
Attn: N. Nemani, L-8J

LU-9J

Re: SPX Corporation former Lindberg Facility  
304 Hart Street  
Watertown, WI 53094

Gentlemen:

As recently discussed between TRC, SPX's environmental consultant, and USEPA's Nathan Nemani, SPX is submitting this information to notify and certify to the Agency and all concerned (the EPA Regional Administrator, the Secretary of the WI DNR, Jefferson County, and the City of Watertown) that SPX intends to conduct a "self-implementing on-site cleanup and disposal of PCB remediation waste" for the captioned site.

SPX had previously received EPA's approval for a partial removal of PCB surficially contaminated concrete flooring and encapsulation of other flooring (40 CFR 761.61 (c)) dated 28 March 2011. As discussed, based on the deteriorating condition of the building and in consultation with the City, SPX has decided to demolish the building and all associated structures and completely remediate the facility in accord with 40 CFR 761.61 (a).

Enclosed is documentation covering the nature of the PCB contamination, the summary of procedures and methods for sampling, characterization and analysis, the location and extent of the contamination, and a cleanup plan including schedule, disposal plan and the demolition and remedial approach.

SPX CORPORATION  
13320 BALLANTYNE CORPORATE PLACE  
CHARLOTTE, NC 28277-2706  
UNITED STATES OF AMERICA

[www.spx.com](http://www.spx.com)




Nathan Nemani, USEPA  
November 19, 2014  
Page 2

Since we believed that we were close to an EPA approval several weeks ago, we are asking for an expedited review of this material in order that our demolition and remediation contractor may continue with his work at the site. Should you need any further information please contact our consultant, Dave McNichol of TRC immediately.

Thank you in advance for your attention to this matter.

Very truly yours,



Walter Galacki  
Director Environmental  
For SPX Corporation, Owner and Operator and Successor in Interest of the  
former SPX Lindberg site

W/enclosures

CC: Jefferson County Health Department, Environmental Health Section  
WI DNR, Remediation and Redevelopment Program  
City of Watertown, J.J. Holloway, PE  
TRC, Dave McNichol  
Nixon Peabody, Al Floro





# **SELF-IMPLEMENTING ON-SITE CLEANUP AND DISPOSAL OF PCB REMEDIATION WASTE**

**SPX LINDBERG FACILITY  
WATERTOWN, WISCONSIN**

*Prepared for*

**SPX CORPORATION**  
Charlotte, North Carolina

*Prepared by*

**TRC**  
Windsor, CT

*date*  
**November 2014**





## TABLE OF CONTENTS

### 1.0 Introduction

#### 1.1 Purpose

#### 1.2 Background

### 2.0 Nature of PCB Contamination

### 3.0 Cleanup Plan

#### 3.1 Bulk PCB Remediation Waste Removal and Disposal

#### 3.2 Schedule

#### 3.3 Verification

#### 3.4 Site Restoration

### 4.0 Recordkeeping

---

### Figure 1. PCB Concrete Removal (after Delta Fig. 6)

## Appendices

- A. Apollo Dismantling Inc.-Waste Management Plan
- B. Delta Consultants Report "Risk-Based Remediation Plan for PCB Contaminated Concrete", December 6, 2010. Report Extract.



## 1.0 INTRODUCTION

### 1.1 PURPOSE

SPX Corporation (SPX) wishes to perform a *Self-implementing on-site cleanup and disposal of PCB remediation waste* at the SPX Lindberg facility located at 304 Hart Street, Watertown, WI 53094. The entire project also involves the complete demolition and remediation of the facility. SPX had received EPA's approval for a risk-based approach under 40 CFR 761.61(c). See EPA letter dated March 28, 2011.

SPX, however, no longer believes the facility is useful in its' deteriorated condition and now wishes to completely demolish the buildings and remediate the site and seeks, with the help of the City of Watertown, to find a redeveloper. Thus, SPX is seeking EPA's approval under 40 CFR 761.61(a) in order to perform a *Self-implementing on-site cleanup and disposal of PCB remediation waste*.

*Certification*

### 1.2 BACKGROUND

Delta Consultants, Shoreview, MN has investigated the Lindberg facility for PCBs and has reported on those investigations. EPA's prior approval was based upon that reporting. TRC has been engaged by SPX to manage/oversee the remediation and demolition. As such TRC and SPX are continuing to rely upon Delta's earlier work and their report "Risk-Based Remediation Plan for PCB-Contaminated Concrete" dated August 2, 2010 and (the subsequent modifications and revisions) it is incorporated herein. For the reader's convenience and reference the material follows this report.

The PCB contamination observed at the former Lindberg facility is believed to have been from the manufacture of electrical transformers during a period from 1953 until 1971. No spill event nor history has been identified through a historical review as well as interviews with former employees. The primary PCB contamination is of concrete flooring (within the building) and to a lesser extent a small area outside the building which is a small loading/shipping pad and adjacent soils. Notably, the PCB contamination is not at depth in the concrete flooring, thus PCB contamination is not expected in the substrate beneath any flooring. See especially the Figures in the Delta Report.

SPX, in conjunction with the facilities full demolition and remediation, will remove all Asbestos Containing Building Materials (ACM), Universal Waste (batteries, lamps-both florescent and metal-halide, mercury in electrical components, CPUs, etc.), decommission all firewater, electrical, water and sewer, remove all oils, lubes, etc. For the demolition all C & D waste will be disposed at the local Subtitle D landfill operated by Waste Management and located in Watertown. The ACM is to be transported and disposed at the Pheasant Run Landfill operated by Waste Management and located in Bristol, WI. Universal waste is destined for Mercury Waste Solutions in Union Grove, WI. And, the PCB concrete along with a minor amount of soil (loading pad area) would be manifested and transported to a Subtitle C Landfill operated by Heritage Environmental Services located in Roachdale, IN.



## 2.0 NATURE OF PCB CONTAMINATION

The nature of the contamination is fully described and explained by Delta in their report. The sampling, the analysis, the PCB results and the graphic (figures) pattern of PCB contamination is all contained in section 2 of their report. SPX and TRC are relying on this information for the Cleanup discussion which follows in section 3. Please see section 2 of the Delta report for a description of the nature of the contamination.



### 3.0 CLEAN UP PLAN

The SPX former Lindberg facility had been principally a manufacturer of industrial ovens, furnaces, and environmental test chambers with an associated office activity. Early in its history the facility had also produced electrical transformers. The manufacturing areas were in some cases added buildings and in other cases large rooms or other functional areas within a given building-see figures. SPX will perform a self-implementing clean up resulting in PCB concentrations for the bulk PCB remediation waste of less than 1 mg/kg and unlimited use for the remaining land after all remediation and demolition are completed (40 CFR 761.61(a)(4)(i)(A)). The proposed clean up includes the removal of PCB contaminated concrete, the removal of a minor quantity of PCB contaminated soils and a loading pad (only outdoor area), and the transportation and disposal of these materials to a RCRA Subtitle C facility all as more fully described below.

#### 3.1 Bulk PCB Remediation Waste Removal and Disposal

SPX intends to remove all of the concrete flooring shown on Figure 1. The contractor hired by SPX, Apollo Dismantling, has mobilized to the site and is currently preparing for the demolition and remediation. At the moment Apollo and its subcontractors are removing all ACM, removing all Universal wastes, collecting all lamps and ballasts, and draining and arranging for utility shutoff and blocks. Once this work is completed Apollo had planned to cut out and remove all PCB concrete for Title C Landfill disposal. See schedule below.

SPX proposes to remove all of the PCB contaminated flooring proposed in the previous approval (all of the areas which were to be removed and all the areas which were to be encapsulated). See relevant parts of Delta section 3. The removal will be in all cases to full floor depth. In addition, SPX proposes to go beyond the limits previously estimated as the 10 mg/kg line by Delta; namely to the next core location (still locatable) where a measured result is less than 10 mg/kg. Thus existing measured values and full depth floor removal ensures the objective is met.

Remaining flooring will then be removed from all areas (rooms and/or buildings) where a PCB floor removal has occurred. The material will be sized and placed in a single on site pile for further use on site, if possible. Prior to any on-site use the pile will be sampled and analyzed to ensure that the material is less than 1 mg/kg PCB. If less than 1 mg/kg PCB, it is candidate material for onsite use to fill any basement voids from the demolition. Should the pile material test between 10 and 1 mg/kg it will not be used onsite but will be disposed into a Subtitle D landfill, either for temporary cover or as fill. Thus any PCB concrete greater than 10 mg/kg (and minor soils quantity) will be disposed at a Subtitle C facility; any PCB concrete between 10 and 1 mg/kg will be disposed in a Subtitle D landfill facility; and,



any PCB concrete less than 1 mg/kg may be retained for use to fill basement voids onsite-or if an excessive quantity exists may also be disposed in a Subtitle D landfill facility.

### 3.2 SCHEDULE

The proposed schedule is as follows:

ACM removal 24 Oct-26 Nov

PCB bulk removal 8 Dec-15 Jan

Lights/ballasts/U waste 17 Nov-15 Dec

Demolition 8 Dec-15 Feb

Restoration Spring 2015

### 3.3 Verification

Verification sampling is necessary for two areas. The removal of the concrete pad in the rail car loading/unloading area (including soils) and the concrete removed pile which will be less than 10 mg/kg and likely less than 1 mg/kg. In both cases EPA Method 8082 will be used for sample analysis. The outdoor excavation will be sampled with 2-sidewalls samples and a bottom invert sample. The concrete pile will be sampled with 6 samples, composited to 2 for analysis.

Since there was no indication in any of the Delta investigation (more than 585 concrete cores) of PCB at floor depth, it is not necessary to sample any substrate below the flooring.

### 3.4 Site Restoration

After completion of all the demolition and remediation activities the site will be restored. The front side walk on Hart Street will remain. The voids of former basement areas will be filled with the concrete from the less than 1 mg/kg pile (assuming it has been verified as above described). After the voids are filled fresh stone will be imported to cover the concrete areas. This will be somewhat crowned to allow that no ponding should occur over time. The property will then be idle until redevelopment can be planned and implemented.




#### 4.0 RECORDKEEPING

A file containing all sampling, analysis, results, graphic depictions of results, shipping and manifesting documents including weight tickets and summaries will be created. Several electronic copies of the record compilation will be made. An electronic copy will be forwarded to USEPA Region 5 PCB Coordinator and to WI DNR PCB Section.

Since it is a cleanup to less than 1 mg/kg PCB no further actions are anticipated.







**RISK-BASED REMEDIATION PLAN FOR**  
**PCB-CONTAMINATED CONCRETE**

**SPX LINDBERG FACILITY**  
**304 HART STREET**  
**WATERTOWN, WISCONSIN**  
**DELTA PROJECT NO. 9M0909245**

**Prepared for:**

**SPX Corporation**  
**13515 Ballantyne Corporate Place**  
**Charlotte, North Carolina 28277**  
**(704) 752-4430**

**Prepared by:**

**Delta Consultants**  
**5910 Rice Creek Parkway, Suite 100**  
**Shoreview, Minnesota 55126**  
**(651) 639-9449**

**December 6, 2010**



## **TABLE OF CONTENTS**

1.0 INTRODUCTION .....	1
1.1 Purpose.....	1
1.2 Background Information.....	1
2.0 NATURE OF CONTAMINATION .....	2
2.1 PCB Wipe Sampling .....	2
2.2 PCB Bulk Concrete Sampling.....	4
3.0 CLEANUP PLAN.....	6
3.1 Bulk PCB Remediation Waste Removal and Disposal .....	7
3.2 Continued Use Authorization .....	8
3.2.1 PCB Source Control .....	8
3.2.2 Decontamination and Coating Methods.....	9
3.2.3 Disposal .....	10
3.3 Bulk PCB Remediation Waste Removal and Disposal .....	10
4.0 RECORDKEEPING .....	11
5.0 REMARKS .....	12

### **List of Tables**

Table 1	PCB Wipe Sample Analytical Results
Table 2	PCB Bulk Concrete Analytical Results

### **List of Figures**

Figure 1	Site Location Map
Figure 2	PCB Wipe Sample Results Map
Figure 3	Concrete Sample Location Map
Figure 4	PCB Results – 0-1 Inch
Figure 5	PCB Results – Deeper Samples
Figure 6	Proposed Areal Extent of Remediation
Figure 7	Proposed Remediation Methods

### **List of Appendices**

Appendix A	Photograph Log
Appendix B	Wipe Sample Analytical Reports
Appendix C	Bulk Concrete Sample Analytical Reports



**RISK-BASED REMEDIATION PLAN FOR**  
**PCB-CONTAMINATED CONCRETE**

**SPX LINDBERG FACILITY**  
**304 HART STREET**  
**WATERTOWN, WISCONSIN**  
**DELTA PROJECT NO. 9M0909245**

**1.0 INTRODUCTION**

**1.1 Purpose**

Delta Consultants (Delta), on behalf of SPX Corporation (SPX), is pleased to present this *Risk-based Remediation Plan for PCB-Contaminated Concrete* for management of polychlorinated biphenyl (PCB)-contaminated concrete at the SPX Lindberg facility located at 304 Hart Street in Watertown, Wisconsin (**Figure 1**). The purpose of this report is to fulfill the application requirements of the Environmental Protection Agency (EPA) Toxic Substance Control Act (TSCA) PCB regulations, 40 CFR 761.61(c) *Risk-based disposal approval* for PCB remediation waste. This report presents the following:

- Site characterization data collected to date;
- Proposed cleanup plan for the facility; and
- Plan for future management of the PCB-contaminated soil and concrete.

Since the proposed cleanup plan includes off-site disposal of PCB remediation waste, engineered controls, and a deed restriction to limit exposure, this Risk-based Remediation Plan is being submitted with the goal of allowing PCB remediation waste to remain at the facility at a concentration of 10 milligrams per kilogram (mg/kg) PCBs.

**1.2 Background Information**

The SPX Lindberg facility is located 1,000 feet east of the Rock River and immediately south of the Chicago, Milwaukee, St. Paul and Pacific railroad in Watertown, Jefferson County, Wisconsin (**Figure 1**). The subject property consists of approximately 5.3 acres of land that is occupied by an approximately 174,000 square foot manufacturing and office building. The Subject Property is bordered by a storage warehouse and railroad tracks to the north, a JohnsonDiversey (formerly U.S. Chemical Company) facility to the east, Hart Street and a parking lot to the south, and residential buildings to the west.

The subject property was originally developed in the early 1920s as a woodworking/manufacturing facility. The majority of the current building infrastructure was constructed



in the 1950s, when it was occupied by Hevi-Duty Electric Company, a manufacturer of electrical transformers, heat treating furnaces, and hot plates. According to historical documents, the combined operations of transformer and furnace manufacturing were moved to Watertown, Wisconsin in 1953. In 1962, a limited portion of the Watertown facility produced the larger transformers with a maximum rating of 2000 KVA. All transformer production at the facility ended in 1971.

According to **nonresponsiv**, former manufacturing supervisor at the facility and facility employee since 1973, recent operations consisted of the manufacture of a wide array of industrial ovens, refrigeration units, environmental test chambers, industrial manufacturing furnaces, and custom products. Manufacturing operations were terminated at the facility in late 2005. The facility is currently unoccupied and largely vacant and is being placed on the market for sale. The potential future facility use is anticipated to remain industrial.

No PCB releases have been reported or are known to have occurred within the facility. The presence of PCB-contaminated concrete was discovered during routine Phase II Environmental Assessment (EA) activities performed on October 1, 2009, prior to SPX placing the facility up for sale. Sampling activities were performed to evaluate for the potential presence of PCBs on the concrete floor surface. Surface wipe sampling was performed in an approximate 60-foot square-based grid pattern throughout the facility. Of the 49 surface wipe samples collected during the initial testing, five samples indicated PCB concentrations greater than 10 micrograms ( $\mu\text{g}$ ) per 100 square centimeters ( $\text{cm}^2$ ) total PCBs.

## **2.0 NATURE OF CONTAMINATION**

Between October 2009 and May 2010, Delta has performed six PCB delineation events at the SPX Lindberg facility to assess the extent and magnitude of PCBs on top of and within the concrete floor. These sampling events included both PCB wipe and bulk concrete sampling and occurred on October 1, October 27, and December 28-30, 2009 and January 25-28, March 16-April 2, and May 4-11, 2010. Photographs taken during the sampling events are presented in **Appendix A**.

### **2.1 PCB Wipe Sampling**

In order to initially characterize the horizontal extent of PCBs on the concrete floor surface, a PCB wipe sampling program was performed. A total of 72 wipe samples were collected



from the floor in an approximate 60-foot square-based grid pattern throughout the facility. The sample locations are shown on **Figure 2**. No floor coverings were compromised during sample collection; sample locations which were proposed in areas covered with carpeting were moved to the nearest non-carpeted area.

The wipe samples were collected using hexane-preserved sorbent pads provided by Pace Analytical Services, Inc. (Pace). The procedure for obtaining a wipe sample for PCB analysis consisted of rubbing the hexane-soaked pad within a 10 cm by 10 cm (100 cm<sup>2</sup>) sample area, using a prescribed wiping pattern that followed the horizontal and vertical axes of the area. The pad was then placed into a 4-ounce amber glass container and the cover was secured tightly on the jar. The wipe samples were submitted to Pace for analysis for PCBs by EPA Method 8082. Laboratory analytical reports for the wipe samples are presented in **Appendix B**.

Analytical results for surface wipe samples are summarized on **Table 1** and **Figure 2**. PCB concentrations ranged from less than the laboratory reporting limit of 1.0 µg per 100 cm<sup>2</sup> to 59.7 µg/100 cm<sup>2</sup>. The PCB concentrations were compared against the TSCA PCB surface cleanup standard of 10 µg/100 cm<sup>2</sup>. Twenty-six of the wipe samples did not indicate the presence of PCBs. Thirty-six wipe samples contained PCBs at concentrations between 1 and 10 µg/100 cm<sup>2</sup>. Ten wipe samples indicated PCB concentrations greater than 10 µg/100 cm<sup>2</sup>. These samples included:

- B1 (59.7 µg/100 cm<sup>2</sup>) and W3 (13.0 µg/100 cm<sup>2</sup>), located near the northeast corner of the "Big Bay" area in the vicinity of a loading area;
- W5 (11.7 µg/100 cm<sup>2</sup>), B4 (23.7 µg/100 cm<sup>2</sup>), W9 (14.4 µg/100 cm<sup>2</sup>), B6 (23.2 µg/100 cm<sup>2</sup>), and W10 (10.8 µg/100 cm<sup>2</sup>), located along the "Heavy Assembly Materials" storage corridor;
- B7 (11.5 µg/100 cm<sup>2</sup>) and W33 (12.4 µg/100 cm<sup>2</sup>), located south of the "Heavy Assembly Materials" storage corridor near the old shipping office; and
- A8 (10.4 µg/100 cm<sup>2</sup>), located in a loading dock area near the southwest corner of the facility.

According to **nonrespo**, the "Heavy Assembly Materials" area, an approximately 16-foot wide by 315-foot room located in the west-central portion of the facility, was formerly used as a staging area for parts and equipment prior to being moved into the product assembly rooms.



## **2.2 PCB Bulk Concrete Sampling**

In order to evaluate whether PCBs have penetrated the concrete floor, 585 bulk concrete samples were collected from 406 locations throughout the facility. The locations of these samples are shown on **Figure 3**.

- Concrete samples B1, B4, B6, B7, and A8 were collected at five locations previously sampled using PCB wipe sampling techniques and exhibiting PCB concentrations exceeding the surface standard of 10 µg/100 cm<sup>2</sup> PCBs.
- Concrete samples 1 through 36 were collected within three areas (the northwest loading area, the southwest loading dock, and the "Heavy Assembly Materials" corridor) previously sampled using PCB wipe sampling techniques and exhibiting PCB concentrations exceeding the surface standard of 10 µg/100 cm<sup>2</sup> PCBs.
- Concrete samples 37 through 171 were collected at approximately 10-foot intervals to expand on the areas where PCB impacted concrete was previously identified at concentrations greater than the bulk concrete standard of 1 mg/kg PCBs.
- Concrete samples 172 through 273 were collected at approximately 20-foot intervals to expand on the areas where PCB impacted concrete was previously identified at concentrations greater than the bulk concrete standard of 1 mg/kg PCBs.
- Concrete samples 274 through 401 were collected at approximately 20-foot intervals throughout the remaining manufacturing portions of the facility.

All manufacturing areas of the facility were sampled with the exception of an 11,000-square foot room in the eastern side and a 1,600-square foot room on the northern side. According to **nonrespo** the room on the eastern side was constructed circa 1978, which was after the date that transformer production ended at the facility (1971), and was used for oven assembly. The room to the north was added in the early 1990s and was used as a cutting room.

Bulk concrete samples were collected in general accordance with EPA Region 1 *Standard Operating Procedure for Sampling Concrete in the Field* (December 30, 1997). The sample holes were advanced using a hand-held rotary hammer/impact drill equipped with 1-inch and ½-inch masonry bits. The 0-1 inch sample was collected by advancing a hole into the concrete to a depth of one inch using the 1-inch bit. Concrete dust generated from the drilling of the sample interval was collected using clean disposable sampling tools and placed into a sample jar. The drill hole was vacuumed thoroughly to prevent cross-contamination between sampling intervals. The hole was further advanced to a depth of



either 3 (or 4) inches using the ½-inch bit and the concrete dust was collected for the 1-3 (or 2-4) inch sample. The drill bits were decontaminated between holes using a soap and water solution and potable water rinse. Three to four holes were advanced at each sample location to obtain a sufficient sample weight for analysis. The bulk concrete samples were submitted for laboratory analysis for PCBs by EPA Method 8082. Laboratories utilized throughout this project include Pace Analytical Services (Minneapolis, Minnesota), TestAmerica (Watertown, Wisconsin), and New Age/Landmark Mobile Analytical Services (New Haven, Michigan). Laboratory analytical reports for the bulk concrete samples are presented in **Appendix C**.

Analytical results for the bulk concrete samples are summarized on **Table 2** and **Figures 4 and 5**. PCBs were detected throughout the manufacturing portion of the facility. PCB concentrations in the bulk concrete samples ranged from below the detection limit to 3,310 mg/kg.

The bulk concrete sample PCB concentrations were compared against the EPA cleanup level of 1 mg/kg PCBs for bulk remediation waste in high occupancy (an average of 6.7 hours or more a week) areas. Of the 406 near-surface (0 to 1 inch deep) concrete samples collected, 294 samples exhibited PCB concentrations above 1 mg/kg PCBs. Deeper samples (1 to 3 inches deep or 2 to 4 inches deep) were collected from 177 of these locations. PCB concentrations were observed to decrease with depth at 176 of the 177 locations, with only 19 of the deeper samples exhibiting PCB concentrations above 1 mg/kg PCBs.

Two locations which exhibited PCB concentrations above 1 mg/kg PCBs at a depth of 1 to 3 inches were sampled from a depth of 3 to 6 inches. Concrete 31, located in the northwest loading area, contained 3,310 mg/kg PCBs in the 0 to 1 inch deep sample and 1,440 mg/kg in the 1 to 3 inch deep sample. No PCBs were detected in the bulk concrete sample collected at a depth of 3 to 6 inches (reporting limit of 0.1 mg/kg for each Aroclor). Concrete sample B6, located near the center of the "Heavy Assembly Materials" area, contained 7.53 mg/kg PCBs in the 0 to 1 inch deep sample and 2.49 mg/kg in the 1 to 3 inch deep sample. No PCBs were detected in the bulk concrete sample collected at a depth of 3 to 6 inches (reporting limit of 0.1 mg/kg for each Aroclor).

Bulk concrete samples were collected from 3 areas located on the outside of the facility: the loading ramp near the southwest corner; the truck ramp located on the east side; and the rail



spur loading area on the north side. Four of the six samples collected from the rail spur loading area (Concrete 36, 39, 40, and 41) contained PCBs at concentrations exceeding 1 mg/kg PCBs. None of the samples collected from the other two areas contained PCBs at concentrations above 1 mg/kg PCBs.

### **3.0 CLEANUP PLAN**

The SPX Lindberg facility is a manufacturing and office building. PCB-contaminated concrete is present throughout the manufacturing portion of the facility. Should a self-implementing cleanup be conducted, a cleanup level for bulk PCB remediation waste of  $\leq 1$  mg/kg would be required without further conditions per 40 CFR 761.61(a)(4)(i)(A). However, an alternative, risk-based cleanup level may be used, pending EPA approval, in accordance with 40 CFR 761.61(c). Based on preliminary conversations with personnel from EPA Region 5 and the Wisconsin Department of Natural Resources (WDNR), a risk-based cleanup level of  $\leq 10$  mg/kg PCBs may be an acceptable site-specific cleanup level for this facility.

A quantitative human health or environmental risk assessment has not been conducted. With the exception of the concrete pad in the rail spur loading area, the PCB contamination is located within the confines of the facility building. Vertical bulk concrete sampling results demonstrate that the PCBs have not penetrated the concrete floor to the underlying soil. Since the contaminated areas which will remain at the property following the proposed cleanup are confined within the physical enclosure of the building, no associated risks to the environment are anticipated. Access to the contaminated areas is provided by entrance doors which are currently locked. Under potential future use conditions, the anticipated use of the building is industrial. The potential occupational exposure in this scenario stems primarily from dermal contact with the contaminated floor.

The proposed site cleanup presented below includes off-site disposal, engineered controls, and a deed restriction to limit exposure. Based on its industrial use and limited accessibility, a risk-based cleanup level of  $\leq 10$  mg/kg is being requested for this facility. Approximately 20,650 square feet of concrete contains PCBs at concentrations greater than 10 mg/kg (**Figure 6**).

The following remediation methods are proposed for the facility in order to address the PCBs at concentrations greater than 10 mg/kg:



- Bulk PCB Remediation Waste removal and off-site disposal of the 700 square-foot concrete pad in the rail spur loading area.
- Continued Use Authorization, which includes cleaning per Subpart S and two coats of epoxy, for the in-place management of 12,150 square feet of PCB-contaminated, bare concrete flooring.
- Continued Use Authorization, which includes superficial cleaning and two coats of epoxy, for the in-place management of 7,000 square feet of PCB-contaminated, epoxy-coated concrete flooring.
- Bulk PCB Remediation Waste removal and off-site disposal of approximately 800 square-feet of PCB-contaminated concrete flooring located at 8 non-contiguous locations.

The locations within the facility proposed to be cleaned by these remediation methods are shown in **Figure 7**.

### **3.1 Bulk PCB Remediation Waste Removal and Disposal**

A 16-foot by 43-foot concrete pad located in the in the rail spur loading area to the north the facility building was found to contain PCBs at concentrations greater than 10 mg/kg (**Figure 7; Appendix A, Photograph 1**). A bulk concrete sample collected from Concrete 36 contained 201 mg/kg PCBs in the 0 to 1 inch sample interval. In order to manage the PCBs in this area, SPX will remove the entire concrete pad in accordance with 40 CFR 761.61(a)(5)(i). The bulk PCB remediation wastes will be managed and disposed off-site in a TSCA-permitted landfill according to the applicable waste classification and disposal regulations as specified under 40 CFR 761.61(a)(5)(i)(B)(2).

Following removal of the concrete pad, a confirmation sample will be collected from the soil beneath the location of Concrete 36. This sample will be analyzed for PCBs by EPA Method 8082. A bulk concrete sample previously collected from Concrete 36 contained 2.29 mg/kg PCBs in the 1 to 3 inch sample interval. Bulk concrete samples collected from the other five locations in the concrete pad did not detect the presence of PCBs at a depth of 1 to 3 inches, so no additional confirmation sampling will be performed beneath the concrete pad. Should the soil sample contain PCBs at a concentration of  $\leq 1$  mg/kg, the cleanup will be considered complete. If the soil sample contains  $>1$  mg/kg PCBs, additional soil sampling would be conducted and soils containing  $>1$  mg/kg PCBs would be removed and disposed off-site along with the concrete pad.



### **3.2 Continued Use Authorization**

The 40 CFR 761.30(p) *continued use of porous surfaces contaminated with PCBs regulated for disposal by spills of liquid PCBs* authorization will be implemented for the in-place management of 19,150 square feet of PCB-contaminated concrete located within the facility. The proposed cleanup level for the work described in this section is  $\leq 10$  mg/kg PCBs.

The proposed cleanup area has been subdivided into two distinct areas with respect to the surface condition of the concrete. The first area consists of 12,150 square feet of bare concrete flooring stretching from the north end of the facility to approximately 440 feet to the south, including the loading dock located on the west side of the building (**Figure 7; Appendix A, Photographs 2 through 5 and 8**). The second area consists of a 7,000-square foot former assembly area near the southern end of the facility (**Figure 7; Appendix A, Photographs 6 and 7**). The floor in this area is covered with a white epoxy coating.

#### **3.2.1 PCB Source Control**

The first step of implementing the 761.30(p) continued use authorization requires the removal of the source causing the release of PCBs. No PCB releases have been reported or are known to have occurred within the facility. The results of the investigation discussed above do not indicate a point source of the PCB contamination. The results of a Phase I Environmental Site Assessment (EA) performed at the facility indicated the potential historical presence of PCBs related to the former manufacture of electrical transformers at the facility. According to information presented in the EA report, dated September 23, 2009:

*The second suspect REC consists of the former manufacture of electric transformers at the Subject Property by the Hevi-Duty Company in the 1950's. Historically, manufacturers of transformers were known to employ dielectric fluids containing polychlorinated biphenyls (PCBs). This condition is characterized as a suspect REC since no direct evidence in the form of spills or releases of transformer fluids are known, nor have any indications of the use of PCB-containing fluids been directly identified at the Subject Property. However, the manufacturing of electric transformers at the Subject Property is indicated in a 1956 Sanborn map and the Hevi-Duty Company is known to have historically used PCB containing transformer fluids at other facility locations in the United States.*

Information regarding Hevi-Duty Company historical operations was obtained from the SolaHD website (<http://www.solaheviduty.com>). According to the company's historical summary, the combined operations of transformer and furnace manufacturing were moved to Watertown, Wisconsin in 1953. In 1962, a limited portion of the Watertown facility



produced the larger transformers with a maximum rating of 2000 KVA. All transformer production at the facility ended in 1971.

### **3.2.2 Decontamination and Coating Methods**

Prior to the initiation of cleanup activities at the facility, all moveable equipment and materials will be removed from the areas to be cleaned. The 12,150 square feet of bare, PCB-contaminated concrete floor will be cleaned in accordance with the double wash/rinse procedure described in 40 CFR 761 Subpart S. This procedure is intended for the decontamination of non-porous surfaces, but 761.30(p) requires that this method be used to prepare PCB-contaminated concrete for encapsulation. Following an initial vacuum to remove loose dust and bird waste, the surface washing steps in this area will include 1) high-pressure steam wash with concrete cleaner/degreaser, 2) potable water rinse, 3) power scrub with a cleaning/degreasing and muriatic acid etchant solution, and 4) high-pressure steam rinse.

The 7,000 square feet of epoxy-coated, PCB-contaminated concrete floors will be cleaned in a manner less stringent than the double wash/rinse procedure. The reason for this is that while bulk concrete samples collected from below the epoxy-coated surface in this area contained elevated levels of PCBs, wipe samples taken from the top of the epoxy-coated surface did not exhibit PCBs above 10 µg/100 cm<sup>2</sup>. Following an initial vacuum to remove loose dust and bird waste, the surface washing steps in this area will include a 1) high-pressure steam wash with concrete cleaner/degreaser, 2) a light scuffing of the epoxy-coated surface with 100+ grit sandpaper, and 3) a final vacuum and rinse.

Following the surface washing activities and once the surface has been allowed to dry for a minimum of 24 hours, an epoxy encapsulant will be placed on the concrete surface according to the requirements of 40 CFR 761.30(p)(1)(iii)(A). Two coats of epoxy will be applied to the floor surface. The two coats of epoxy will consist of contrasting colors so that any wearing of the topcoat can be detected. In the area where a white epoxy coating already exists, one additional coat will be applied in a contrasting color.

Once the epoxy has dried, labels will be placed on the encapsulated floor surfaces to indicate that PCBs remain in the underlying concrete as specified under 40 CFR 761.30(p)(1)(iii)(B). The labels, described in 761.45, will be applied at the entrances, corners, and central portions of the encapsulated area.



### **3.2.3 Disposal**

Wastes generated during the double wash/rinse procedure and encapsulation may include water mixed with detergent, water mixed with spent degreaser, used absorbent materials, and other equipment. These wastes will be managed according to applicable waste classification and disposal regulations as specified under 40 CFR 761.378(c).

### **3.3 Bulk PCB Remediation Waste Removal and Disposal**

Besides the 19,150 square feet of PCB-contaminated concrete described above, there were eight non-contiguous concrete sample locations exhibiting PCB concentrations greater than 10 mg/kg (**Figure 7**). These locations include the following:

- Concrete 53 - 12.67 mg/kg PCBs at 0-1 inch, 1.06 mg/kg PCBs at 1-3 inches (Wipe B5 had 2.0 µg/100 cm<sup>2</sup> PCBs);
- Concrete 103 - 40.0 mg/kg PCBs at 0-1 inch, non-detect at 1-3 inches;
- Concrete 178 - 11.00 mg/kg PCBs at 0-1 inch, (Wipe A7 had 4.6 µg/100 cm<sup>2</sup> PCBs);
- Concrete 230 - 11.50 mg/kg PCBs at 0-1 inch, non-detect at 2-4 inches (Wipe C3 had 5.6 µg/100 cm<sup>2</sup> PCBs);
- Concrete 239 - 22.0 mg/kg PCBs at 0-1 inch, (Wipe C6 was non-detect);
- Concrete 252 - 11.0 mg/kg PCBs at 0-1 inch, non-detect at 2-4 inches;
- Concrete 272 - 10.3 mg/kg PCBs at 0-1 inch, non-detect at 2-4 inches (Wipe C4 had 4.5 µg/100 cm<sup>2</sup>); and
- Concrete 370 - 16.0 mg/kg PCBs at 0-1 inch.

Given the limited areal and vertical extent of PCBs in these eight locations, SPX will cut out and remove the 10-foot by 10-foot (100-square foot) section of concrete floor surrounding each sample location (**Figure 7**). The entire thickness of the concrete floor will be removed. The bulk PCB remediation wastes will be managed and disposed off-site in a TSCA-permitted landfill according to the applicable waste classification and disposal regulations as specified under 40 CFR 761.61(a)(5)(i)(B)(2). Since the entire thickness of the concrete floor will be removed in these areas, no confirmation sampling will be conducted.



It is anticipated that the cleanup will begin within approximately one month of EPA authorization and will take approximately one month to complete. The following is an estimated timeline to complete the site cleanup:

<b>Item</b>	<b>Date</b>
<i>EPA Approval</i>	<i>January 2011</i>
<i>Initiate Site Cleanup</i>	<i>February 2011</i>
<i>Complete Site Cleanup</i>	<i>March 2011</i>
<i>Reporting and Deed Restriction Filing</i>	<i>May 2011</i>

#### **4.0 RECORDKEEPING**

As requested in 40 CFR 761.61(a)(3)(i)(E), a file containing all sampling plans, sample collection procedures, sample preparation procedures, extraction procedures, and instrumental/chemical analysis procedures used to assess the PCB contamination at the facility will be maintained at the facility and will be available for EPA inspection. The written certification, signed by a representative of SPX as both property owner and party conducting the cleanup, will be submitted as a separate document.

Because cleanup activities include the use of an encapsulant and PCB-contaminated concrete will remain at concentrations which exceed the regulatory cleanup levels, a deed restriction will be recorded within 60 days of the completion of the cleanup activities in accordance with 40 CFR 761.61(a)(8)(i). A written certification indicating that the deed restriction has been filed will be submitted to the EPA Regional Manager.

Long-term management of the PCB-affected concrete will be necessary. An operations and maintenance management plan will be developed to maximize employee protection. Components of the management plan will include training information for facility workers to inspect the encapsulant for wear and damage, procedures for repairing the encapsulant as needed, and a safety plan for workers in the event that they need to penetrate the encapsulant and drill into the concrete. The management plan will also include a plan for addressing the ultimate removal and disposal of PCB-contaminated concrete and soil remaining beneath the encapsulant for the point in time when the property is adapted for another use or the building demolished.



### **5.0 REMARKS**

The recommendations contained in this report represent Delta's professional opinions based upon the currently available information and are arrived at in accordance with currently acceptable professional standards. This report is based upon a specific scope of work requested by the client. The contract between Delta and its client, SPX Corporation, outlines the scope of work, and only those tasks specifically authorized by that contract or outlined in this report were performed. This report is intended only for the use of Delta's client and anyone else specifically identified in writing as a user this report. Delta will not and cannot be liable for unauthorized reliance by any other third party. Other than as contained in this paragraph, Delta makes no express or implied warranty as to the contents of this report.

This report was prepared by **DELTA CONSULTANTS**.



Karen J. Thole, P.G.  
Project Hydrogeologist



Peter J. Schwalbach  
Project Manager





Writers Direct Dial: 704-808-3751  
Writers Direct Fax: 704-752-4578  
E-Mail Address: [walter.galacki@spx.com](mailto:walter.galacki@spx.com)

October 22, 2014

USEPA  
Region 5  
TSCA/PCB Section  
77 West Jackson Boulevard  
Chicago, IL 60604-3590  
Attn: N. Nemani, L-8J

Re: SPX Lindberg Facility  
304 Hart Street  
Watertown, WI 53094

Gentlemen;

As recently discussed between TRC, SPX's environmental consultant, and USEPA's Nathan Nemani, SPX Corporation has had a change in plans and now intends to completely demolish and remediate the named facility. SPX received EPA approval (March 28, 2011) for a partial removal of PCB contaminated flooring along with cleaning and encapsulating other PCB impacted floor areas. Based on the deteriorating condition of the building and a request from the City for building evaluation, SPX is requesting EPA's modified/amended approval for a complete removal of all flooring with PCB contaminant concentrations greater than 10 mg/kg. SPX believes that a complete removal of the PCB impacted areas above 10 mg/kg and complete demolition of the facility represents a permanent remedy for the facility and is therefore a better and more complete remedial approach.

SPX proposes to remove all of the PCB contaminated flooring proposed in the previous approval and a small additional portion. As discussed, SPX is relying upon the work performed by Delta Consultants, "PCB Assessment Report" dated August 11, 2010; in particular Figures 6 and 7 from that and related reports which were previously submitted to EPA and are attached for reference. Rather than estimate a 10 mg/kg line (as the shaded areas on the Figures have done), SPX is

SPX CORPORATION  
13320 BALLANTYNE CORPORATE PLACE  
CHARLOTTE, NC 28277-2708  
UNITED STATES OF AMERICA

[www.spx.com](http://www.spx.com)



N. Nemani  
October 22, 2014  
Page 2

proposing to have its' contractor remove the flooring to the next measured core where there has been a below 10 mg/kg measurement. Since there has been no use of the building in the intervening time, the bright white core patches are easy to locate. Please see the marked Figures 6 and 7 attached. SPX believes this increased floor removal will provide more certainty that removal has occurred to less than 10 mg/kg. [Also, such an approach will reduce the need for confirmation sampling after concrete removal.]

SPX believes this is the most prudent and practical approach because most of the remainder of the shaded floor areas are bounded by walls providing a practical limit for removal. The small area outside the rail/truck loading pad (see No. 2) will be subject to a removal until confirmed by post-excavation samples.

At this time SPX is considering removal and disposal of the impacted concrete at either the Heritage or U S Ecology facilities. (No shipment would occur until and unless EPA has been notified and approval secured.)

Since SPX has recently funded this work, received local approval from the City, and hired a contractor, your earliest response would be most appreciated. Short term work while we await your response will include asbestos related removal and demolition related preparation activities. SPX wishes to thank you for your consideration and review. Please call me directly or Dave McNichol of TRC (office: 203-876-1453, cell: **nonrespons**) if you have any questions.

Very truly yours,




Walter Galacki  
Director, Environmental

cc: D. McNichol -TRC  
S. DeFranks - Apollo


Enclosure



Delta Health Research Institute










March 2006



New Removal Limit









Re: SPX--- PCB Approval Letter   
Peter Ramanauskas to: Neman.Nate

03/02/2011 02:43 PM

Nate,

Thanks for the opportunity to review your draft. I've made some edits and comments in Track Changes in the attachment.

One main question: we were OK with allowing no coatings for concrete where detections were < 10 mg/kg given an Industrial Use restriction? Did you check in with Mario on the revised plan? My notes say there were no wipe samples at the facility > 10 ug/100cm<sup>2</sup> - is that correct? Also, maybe we should ask to see a draft of the use restriction?

Lastly, once we're comfortable with our draft, do you think it would be good to share it with SPX?

Let me know if you'd like to discuss.

Thanks!  
Peter



SPX Lindberg Wisc. Risk based Remediation Plan EPA Approval Ltr FINAL 022511 PR Edits.doc

Nate Neman

Peter: Please look at the Attached letter and if it...

02/25/2011 03:44:31 PM

From: Nate Neman/R5/USEPA/US  
To: Peter Ramanauskas/R5/USEPA/US@EPA  
Date: 02/25/2011 03:44 PM  
Subject: SPX--- PCB Approval Letter

Peter:

Please look at the Attached letter and if it is OK, and offer any suggestions/comments on the same.

Following this step, my intent is to initiate the sign-offs next week and send it out by 3/10 if possible.

Thanks

Nate

[attachment "SPX Lindberg Wisc. Risk based Remediation Plan EPA Approval Ltr FINAL 022511.doc" deleted by Peter Ramanauskas/R5/USEPA/US]

NATE NEMANI, P.E.  
RCRA CORRECTIVE ACTION PROJECT MANAGER



LAND AND CHEMICALS DIVISION  
REMEDATION AND REUSE BRANCH,  
U. S.EPA, REGION 5 ,  
77 W JACKSON Blvd, CHICAGO,ILLINOIS,60604, Mail Code: LU-9J  
(312) 886-3224 (PHONE)  
(312) 692-2176 (FAX)  
nemani.nate@epa.gov (e-mail address)



LU-9J

Mr. Daniel McGrade  
Director, Environmental,  
SPX Corporation  
13515 Ballantyne Corporate Place  
Charlotte, North Carolina, 28277

RE: Approval for Risk-Based Remediation/ Cleanup and Disposal of PCB  
Contaminated Concrete at the SPX Lindberg Facility – 304 Hart Street,  
Watertown, Wisconsin

Dear Mr. McGrade:

The U.S. Environmental Protection Agency, Region 5 (EPA) has reviewed SPX Lindberg's Watertown, Wisconsin facility's (SPX), Risk Based Remediation Plan (Plan) dated August 11, 2010 and the subsequently revised plan of December 6, 2010 prepared and submitted by Delta Consultants of Shoreview, Minnesota, on behalf of SPX Corporation for the subject facility. The Plan is hereby approved with the attached conditions.

The Plan calls for a Risk Based Remediation/Clean-up <sup>and</sup> for the management of Polychlorinated Biphenyl (PCB) impacted concrete at SPX's subject manufacturing facility in Watertown, Wisconsin in accordance with EPA Toxic Substance Control Act (TSCA) PCB regulations 40 CFR 761.61(c). Specifically, the application asks for a Risk Based disposal approval for PCB Remediation waste. A Risk Based clean up level of  $\leq 10\text{mg/kg}$  is proposed based on its Industrial use classification and limited accessibility.

Based on facility wide sampling it was determined that approximately 20,650 square feet of concrete contains PCB at concentrations greater than 10 mg/kg. The following remediation methods/plan-s ~~is are~~ being proposed for the facility to address the areas with PCB concentrations greater than 10 mg/kg:-

- a) Bulk PCB Remediation Waste Removal and off-site disposal of a 700 square foot concrete pad in the rail spur loading area.
- b) ~~Request for (i)~~ Continued Use Authorization ~~following~~ cleaning per ~~Subpart S~~ and (ii) ~~two coats of epoxy for in place management §761.30(p)~~ of 12,150 square feet of PCB contaminated bare concrete flooring.
- c) ~~Request for~~ Continued Use Authorization ~~following~~ superficial cleaning and two coats of new epoxy for in place management of 7,000 square feet of PCB contaminated, previously epoxy coated concrete flooring.



- d) Bulk PCB Remediation Waste Removal and off-site disposal of approximately 800 square feet of PCB contaminated concrete flooring located at eight non-contiguous locations each 10 feet by 10 feet.

This approval is granted in accordance with the federal PCB regulations codified at 40 CFR §761.61(c), under which the Regional Administrator may approve a risk-based disposal approval application, if it is found that the method will not pose an unreasonable risk of injury to human health or the environment. -The Regional Administrator has redelegated this approval authority to the Director of Land and Chemicals Division. PCB remediation and clean-up activities will be conducted in accordance with the report dated August 11, 2010 and subsequently revised per the e-mail and its attachment dated December 6, 2010.

SPX is responsible for ensuring continued compliance with all applicable provisions of the Toxic Substances Control Act (TSCA), the federal PCB regulations and the Conditions of this approval, attached herewith. All conditions of this approval and other applicable requirements of TSCA and its regulations will continue to apply to the site after any transfer in ownership.

Please do not hesitate to call Nate Nemani, of my staff, at (312) 886-3224, if you have any questions regarding this approval.

Sincerely,

Bruce F. Sypniewski  
Acting Director  
Land and Chemicals Division

Enclosure

cc: Jeff Ackerman, Wisconsin Department of Natural Resources (WDNR)



## APPROVAL CONDITIONS

### A. Authorized Remedial Action

1. SPX is authorized to cleanup and dispose of PCB remediation waste at its facility in Watertown, Wisconsin facility located at 304 Hart Street (Site) according to the procedures described in the August 11, 2010 report titled Risk- Based Remediation Plan for PCB Contaminated Concrete and the subsequent revisions described in the December 6, 2010 email and Attachments. In addition, the following requirements need to be adhered to:

a) **Bulk PCB Remediation Waste Removal and Disposal:**

SPX will remove a 16 foot by 43 foot concrete pad located in the rail spur loading area. ~~The disposal of the material will be~~ at a TSCA permitted Landfill in accordance with regulations under 40 CFR §761.61(a)(5) (H)(B)(2). In addition to the rail spur loading area, eight (8) non-contiguous concrete sample locations will undergo similar removal and disposal. Given the limited area and vertical extent of PCBs in these eight locations, SPX will cut out and remove the entire thickness of a 10 foot by 10 foot concrete floor surrounding each sample location where the concentrations exceeded 10 mg/kg. ~~The disposal of the material will be~~

Formatted: Font: Italic

Comment [PR1]: Describe how this material will be properly disposed.

b) **Continued Use Authorization:**

In accordance with requirements set forth in 40 CFR §761.30(p), porous surfaces contaminated by PCB will be managed with a target clean-up level of  $\leq 10$  mg/kg and as per the procedures outlined in the December 6, 2010 e-mail.

Comment [PR2]: Should this be 'contaminated surfaces > 10 ppm'? Are all areas where wipe samples are > 10 ug/100 cm<sup>2</sup> included for wash/rinse/epoxy coating?

Comment [PR3]: Better to say "Attachments to the email"?

c) **Property Use and Restrictions and Notice:**

Within 60 days of completion of the above approved removal activities in accordance with 40 CFR 761.61 (a) (8) (i), SPX will record, in accordance with state law, a notation to the deed for the Facility. A written certification indicating that the deed restriction has been filed will need to be submitted to the EPA Regional Administrator.

Comment [PR4]: We should indicate that it needs to be an industrial use restriction. Maybe we should see a draft of the deed restriction?

### B. Inspection, Maintenance and Monitoring

Plans for the Long term management of the PCB affected concrete shall be put in place for implementation as needed. An Operations and Maintenance Plan shall be developed for minimizing human exposures. This shall include training of workers for inspecting the encapsulant for wear and damage, procedures for repairing the encapsulant as needed and a Safety plan for workers in case repair of the area is required. The management plan shall also include addressing the ultimate removal and disposal of PCB Contaminated concrete and soil remaining beneath the encapsulant in the event of building demolition or renovation. Any

*Draft of the  
Deed Restriction*

*revised Section  
3.0 "Cleanup  
Plan of  
of the Risk-Based Remedial  
Plan, 8/11/10*



concrete containing PCB at concentrations > 1 ppm must be disposed of per 40 §CFR 761.61, ~~for reconstruction of a different structure,~~

**C. Change of Ownership**

1. At least 45 days before conveying, in any manner, ownership or responsibility of the Facility or underlying property, SPX will notify EPA, Region 5, of its intent to convey such ownership or responsibility. Such notice will include the date of the intended conveyance, and the name, address, and phone number of the intended new owner or responsible person. If the conveyance is being made to a corporate entity, this notice will also include the name of a contact person.
2. At least 30 days before such conveyance, SPX will submit to EPA, Region 5, a notarized affidavit signed by the intended new owner or responsible person who states that such person will abide by the provisions of this Risk-Based Approval granted to SPX for this Facility.

**D. Recordkeeping and Reporting**

1. SPX will maintain all records and documents as required by 40 CFR Part 761.
2. SPX will submit a Closure Certification Report to EPA and WDNR within 90 days of completion of the activities described under this Approval. At a minimum, the report will include: a discussion of project activities, as-built specifications, sampling analytical results, copies of the accompanying analytical chains of custody, quality control/quality assurance checks, an estimate of the quantity of PCBs removed and disposed of off-site, and copies of manifests.





August 13, 2010

Ms. Susan Hedman  
Regional Administrator  
US EPA Region 5  
77 West Jackson Boulevard  
Chicago, IL 60604

Mr. Matthew Frank  
Secretary  
Wisconsin Department of Natural Resources  
P.O. Box 7921  
Madison, WI 53707-7921

Mr. Jeff Ackerman  
Wisconsin DNR South Central Region  
Division of Air and Waste  
Remediation and Redevelopment  
3911 Fish Hatchery Road  
Fitchburg WI 53711

Subject: *Risk-Based Remediation Plan Written Certification*  
SPX Lindberg Facility  
304 Hart Street  
Watertown, Wisconsin  
Delta Project No. 9M0909245

Dear Ms. Hedman, Mr. Frank, and Mr. Ackerman:

The purpose of this correspondence is to provide written certification as required in the Code of Federal Regulations, Title 40, Volume 29, Part 761.61(a)(3)(i)(E) for the risk-based cleanup at the SPX Lindberg facility located at 304 Hart Street in Watertown, Wisconsin. A document entitled *Risk-Based Remediation Plan for PCB-Contaminated Concrete*, dated August 11, 2010, (sent separately) has been submitted for your review.


As a representative of SPX, which is both the owner of the property and the party conducting the cleanup, I certify that a file containing copies of all sampling plans, sample collection procedures, sample preparation procedures, extraction procedures, and instrumental/chemical analysis procedures used to assess or characterize the PCB contamination at the facility are maintained at the facility and are available for EPA inspection.

If you have any questions regarding this information or the project in general, please contact Ms. Karen Thole of Delta Consultants at (651) 697-5203.

Sincerely,

**SPX Corporation**

SPX CORPORATION  
13515 BALLANTYNE CORPORATE PLACE  
CHARLOTTE, NC 28277  
UNITED STATES OF AMERICA

  
Virginia Sunde  
Assistant Director, Environmental

cc: Karen Thole, Delta-Milwaukee

RECEIVED  
DIVISION FRONT OFFICE

AUG 18 2010

LAND AND CHEMICALS DIVISION  
U.S. EPA - REGION 5

RECEIVED

AUG 18 2010

U.S. EPA  
OFFICE OF REGIONAL ADMINISTRATOR

AUG 18 2010



